

PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING & SHOP FOR MR. SOUNDARAJAN AT S. NO 417/3 OF THANDARAI VILLAGE AVADI TOWNSHIP, MADRAS, CHENNAI DISTRICT, SRIPERUMBUDUR TALUK.

SPECIFICATION:

FOUNDATION: STONE JELLY CEMENT CONCRETE OVER A LAYER OF SAND FILLING
BRICK WORK: 3" STOCK BRICKS IN CM 1:5 IN FOUNDATION & BASEMENT AND 1:5 IN SUPERSTRUCTURE.
ROOFING: K.C.C ROOF SLAB 4 1/2" THK. 1:2:4 WITH 0.8% OF REINFORCEMENT WITH NECESSARY WATER PROOFING.
FLOORING: BRICK JELLY IN LIME OVER A LAYER OF SAND FILLING AND TOP PLASTERED FINISHED SMOOTH.
PLASTERING: WALLS & CEILING IN 1/2" THK. IN CM 1:6

SCHEDULE OF JOINERY:

D	3'3" X 7'0"	0.99 X 2.13	DOOR
D1	3'0" X 7'0"	0.91 X 2.13	DOOR
D2	2'6" X 7'0"	0.78 X 2.13	DOOR
W	6'0" X 4'6"	1.83 X 1.37	WINDOW
W1	4'0" X 4'6"	1.21 X 1.37	WINDOW
W2	2'0" X 3'6"	1.21 X 1.06	WINDOW
RS	4'0" X 7'0"	1.52 X 2.13	ROLLING SHUTTER

REFERENCE:

PROPOSALS: [Symbol]
EXG ROAD: [Symbol]
SITE BOUNDARY: [Symbol]
PLOT AREA: 2138 SQ. FT. 198.62 m²
BUILTUP AREA: 622 SQ. FT. 57.42 m² TOILET: 74 SQ. FT. 7 m²

OWNER

V. Venkatesan

V. VENKATESAN, B.E., M.Sc., M.I.E.
 CIVIL ENGINEER.
 LICENSED SURVEYOR.
 AVADI TOWNSHIP.
 Office: 3, Paper Mills Road, First Floor.
 NEAR PERAMBUR CHURCH - 600 011
 LICENSED SURVEYOR

