

PROPOSED RESIDENCE OF G.ANBUKKU  
 ARASAN AT PLOT No 34 & 35 OF S No 567/1  
 & 8/1 No 55 MANAPAKKAM VILLAGE  
 SRI PERUMPUDUR TALUK CHINGALPAT  
 DISTRICT scale: 1"=8'-0"

**SCHEDULE OF JOINERY**

D <sub>1</sub> : FLUSH DOOR	3'-6" x 7'-0"	(1.1 x 2.1)
D <sub>2</sub> : DOOR	3'-0" x 7'-0"	(0.9 x 2.1)
D <sub>3</sub> : PANELLED DOOR	2'-6" x 7'-0"	(0.7 x 2.1)
W <sub>1</sub> : GLAZED WINDOW	6'-0" x 4'-6"	(1.8 x 1.3)
W <sub>2</sub> : " "	6'-0" x 3'-0"	(1.2 x 0.9)
V : VENTILATOR	3'-0" x 2'-6"	(0.9 x 0.7)
F/W : FRENCH WINDOW	4'-0" x 7'-0"	(1.2 x 2.1)

**SPECIFICATION**

DEPTH OF FOUNDATION 3' WIDTH 3' R.C.C. 1:4:8  
 6" THICK FLOORING CEMENT CONC. FLOOR  
 USING BRICK JELLY (3/4) SUPER STRUCTURE  
 BRICK WORK 9" THICK USING 1:5 MIX MORTAR  
 PLASTERING 1:4 MIX LINTEL, SUNSHADE, ROOF  
 SLAB LOFT ALL ARE IN R.C.C. 1:2:4 USING  
 TOR STEEL WEATHERING COURSE LAID TO SLOPE

**PROPOSAL**

ROAD	
BOUNDARY	
SEWAGE	

GROUND AREA : 1806 Sq. Ft. (or) 167.77 m<sup>2</sup>  
 PLINTH AREA : 640 " " (or) 59.45 m<sup>2</sup>

*G. Anbukku*  
 OWNER

*P.C. Gowry Shankar*  
 P.C. GOWRY SHANKAR, B.E., S.I.C.Jr.  
 Civil & Structural Engineer.  
 Class-I. Licensed Surveyor No: 297  
 Corporation of Madras,  
 Off: 15/1, Govindan Road,  
 Near Srinivasa Theatre,  
 West Mambalam, MADRAS-33.

LICENCED SURVEYOR

