



AREA STATEMENT	S. FT.	M. S.
PLOT AREA	7776.6	722.4
GROUND FLOOR AREA	2634.0	263.3
TYPICAL FLOOR AREA (2834 x 3)	8502.0	789.9
TOTAL	11336.0	1053.2

No	Width	Height	Description
D	3'-3"	7'-0"	7 M. PANELLED DOOR
D1	3'-0"	7'-0"	"
D2	2'-6"	7'-0"	"
W	6'-0"	4'-6"	T.M. GLAZED WINDOW
W1	4'-0"	4'-6"	"
W2	3'-0"	3'-0"	"
V	2'-6"	2'-6"	GLAZED VENTILATOR

- Specification**
- FOUNDATION CONCRETE IN P.C.C. 1:4:8 WITH 1" BROKEN GRANITE S&S
 - C.C. 1:2:4 FOR ALL R.C.C. WORKS WITH BROKEN GRANITE S&S
 - 3" TK (230mm) BRICKWORK IN C.M. 1:3
 - 4 1/2" TK (115mm) BRICK WORK IN C.M. 1:4 WITH 6mm M.S. RODS AT EVERY THIRD COURSE
 - PLASTERING THE CEILING AND EXPOSED CONCRETE SURFACE IN C.M. 1:3
 - PLASTERING THE WALLS IN C.M. 1:4
 - WEATHERING COURSE IN BRICK JELLY LIME CONCRETE 3" AVERAGE TK WITH A COURSE OF FLAT TILES IN C.M. 1:3
 - FLOORING WITH HYDRAULICK PRESSED MOSAIC TILES SET IN C.M. 1:4 AND SKIRTIN 5" HEIGHT
 - THE O.H.T. IS HERMETICALLY SEALED.

- Legend:**
- PROPOSED CONSTRUCTION SHOWN THUS
 - BOUNDARY LINE
 - ROADS
 - SEWER LINE
 - WATER LINE

Scale 1in = 8ft Date 31-08-90

Job Title:
 PROPOSED APARTMENTS AT PLOT NO: 97, 18th STREET, NANGANALLUR, ULLAGARAM VILLAGE, MADRAS-600 016. BEARING S.No: 99(1) FOR Mr. M.S.SRINIVASAN.

Architect:
 S. Subramaniam M. Arch, A.I.A.,
 Architect & Interior Designer,
 Licensed Class-1, Surveyor No.90,
 8/1 Vidyanaraya, II Main Road,
 Kasturibai Nagar, Adyar,
 Madras-600 020 Ph: 411305.