FRONT ELEVATION

FRONT ELEVATION

PROPOSED ADDITION IN SECOND FLOOR PLANNING PERMISSION No. C.P.P.C/125/91 APPROVED SUBJECT TO THE CONDITIONS IMPOSED IN C.P.P.C/1942/91 DATED 5/8/91 FOR GROUND FLOOR & FIRST FLOOR DEMOLISHED

BUNGALA STREET (SERVICE ROAD)

100'0" RING ROAD

SITE PLAN (scale 1"=16'0")

SECTION A-A

SECTION BB

R.C.C. COLOUMN FOOTING DETAIL (not to scale)

R.C.C. COLOUMN DETAIL not to scale

GROUND FLOOR PLAN

TILED SHED PLAN

SECTION C-D

SECTION C-D

FIRST FLOOR PLAN

SECOND FLOOR PLAN

FIRST FLOOR PLAN

GROUND FLOOR PLAN

KEY PLAN not to scale

SITE PLAN not to scale

PROPOSED BUILDING IN SUB DIV NO.50. DOOR NO9. BUNGALA STREET T.S. NO2,59 BLOCK NO 3,4 OF EKKATTUTHANGAL MADRAS 97

N

SPECIFICATION

Foundation, plinth beam, roof slab, main beams are of r.c.c. 1:2:4. Plastering of walls are of 1:4 cement mortar. Plastering of ceiling items are of 1:3 c.m. Brick works are of 1:5 c.m. All wood works are of seasoned teak wood.

TOTAL FLOOR AREA = 12360 sq. ft.

Proposed building - areas

Proposed ground floor 2106.10 sq ft
" first floor 2559.67 "
" second floor 2559.67 "
Total floor area 7225.44 sq.ft.

Addition to the existing building - areas

Existing ground floor 1774.40 sq.ft.
Existing first floor 2363.75 "
Proposed second floor 2363.75 "
Total floor area 6442.38 sq.ft.

SHEDULE OF JOINERY

D	DOOR	5'0" X 7'0"
D1	"	4'0" X 7'0"
D2	"	2'6" X 6'6"
D3	"	3'0" X 7'0"
D4	"	3'5" X 7'0"
D5	"	2'6" X 7'0"
W	WINDOW	4'0" X 4'6"
W1	"	5'0" X 4'6"
W2	"	3'0" X 4'6"
V	VENTILATOR	3'0" X 2'0"
V1	"	2'0" X 2'0"

PROPOSED BUILDING — ROAD SHOWN
EXISTING BUILDING
TO BE DEMOLISHED
BOUNDRY

scale 1=8'0"

OWNER

LICENSED SURVEYOR

A. C. RAJAN Arch, A.I.I.A; M.T.P. F.I.V. A.L.S.
8- Varadarajulu roads
Egmore, Madras-8.

A. C. RAJAN
LICENSED SURVEYOR
No. 1185
MADRAS