Revised Sanctioned Plan
C.P.U. 6.10.92

DRAWING BY

Planning Permit No. C/49/1463/92 Dt. 6.10.92

APPROVED

SUBJECT TO GENERAL CONDITIONS IN No. C/49/1463/92 Dt. 6.10.92

SCHEDULE

D - DOOR 1.35 X 2.10
D - DOOR 1.35 X 2.10
W - WINDOW 1.35 X 1.20
W - WINDOW 1.80 X 1.20
V - VENTILATOR 0.75 X 0.45
V - VENTILATOR 1.35 X 0.60

PROPOSED CONSTRUCTION OF PRIYANANDA VIDYALAYA PRIMARY SCHOOL BUILDING AT DT.PNO.143/3 & S.No 143/3 (PT), SANKARA NAGAR PANNAL VILLAGE, CHINGLEPUT DT.

| SCALE | NORTH | DRG. No. |
|---|---|---|
| 1:100 | | |

PROPOSED CONSTRUCTION
SITE BOUNDRY
ROAD

| | SQ.MTS | SQ.FT |
|---|---|---|
| SITE AREA : | 645.9 | 6,230.30 |
| PROPOSED BUILT UP AREA : | 432.79 | 4,657.80 |

OWNER

R. VENUGOPAL, B.E. (HONS)
CONSULTING CIVIL ENGINEER
LICENSE SURVEYOR CLASS I
CORPORATION OF MADRAS
LICENCED BUILDING SURVEYOR
NANGANALLUR (LAKE AREA)
MADRAS-600 061

FRONT ELEVATION

100'9" (30.70M)

20'-0" (6.10M) | 20'-0" (6.10M) | 20'-0" (6.10M) | 20'-0" (6.10M) | 20'-6" (6.10M)

OFFICE ROOM | CLASS ROOM | CLASS ROOM | CLASS ROOM | CLASS ROOM

CLASS ROOM | CLASS ROOM | CLASS ROOM | CLASS ROOM | CLASS ROOM | CLASS ROOM

BORE WELL

6'0" WIDE CORRIDOR

79'-11½" (22.28M)

GROUND FLOOR PLAN

SECTION X-X

12.5 TK RCC SLAB (1:2:4) MIX | WEATHERING COURSE OVER BRICK JELLY | 4½" BRICK WORK | 9" BRICK WORK WITH C.M. (1:6) | 0.23 TK RCC LINTEL (1:2:4) MIX | TO SEPTIC TANK | SAND FILLING | CEMENT FLOORING OVER 10 CM THK (1:2:4) CONCRETE | 0.10 TK RCC (1:2:4) MIX OVER 10 CM TK SAND FILLING

SECTION 'AA'

LOCATION PLAN

4th STREET 30'0" (9.14M) WIDE

136'-0" (41.45M)

10'

PEPPE OPEN SPACE

100'6" (30.70)

PROPOSED SCHOOL BUILDING

SEPTIC TANK | SOAK PIT | BORE WELL | PLAY GROUND

8th STREET 30'0" (9.14M) WIDE

10th STREET 30'0" (9.14M) WIDE

16'6" (4.87M) | 20'0" (6.09M) | 21'3" (7.39M)

138'-0" (42.06M)

SITE PLAN (1:200)

9" BRICK WORK | 6'0" | 6'0" | A | B

SEPTIC TANK (PLAN) 6'0"

MANHOLE 4" RCC SLAB | INLET | RCC COVER | OUTLET 4" DIA | SAND | RUBBLE

PSC 1:48 SECTION AB | SOAK PIT