



**SCHEDULE OF JOINERY**

No	Width	Height	Description
D1	990	2133	T.W. Panel Door
D2	914	2133	"
D3	762	2133	"
W	1829	1371	TW Glazed window
W1	1219	1371	"
W2	914	914	"
V	762	762	TW Glazed ventilator

*A/1908/92*  
*22/10/92*

**Specification**

- FOUNDATION CONCRETE IN P.C.C. 1:4:8 WITH 1% BROKEN GRANITE JELLY
- P.C.C. 1:2:4 FOR ALL R.C.C. WORKS WITH BROKEN GRANITE JELLY
- 9" X (230MM) BRICK WORK IN C.M. 1:5
- 4 1/2" X (110MM) BRICK WORK IN C.M. 1:4
- PLASTERING THE CEILING AND EXPOSED CONCRETE SURFACE IN C.M. 1:5
- PLASTERING THE WALLS IN C.M. 1:4
- WEATHERING COURSE IN BRICK JELLY LINE (CONCRETE 2" AVERAGE TH WITH A COURSE OF FLAT TILES IN C.M. 1:5)
- FLOORING WITH HYDRAULIC PRESSED MOSAIC TILES SET IN C.M. 1:2 AND SKIRTING 5" HEIGHT
- THE O.H.T IS HERMETICALLY SEALED

**Notes**

- PROPOSED CONSTRUCTION SHOWN THIS
- BOUNDARY LINE
- ROAD
- SEWER LINE
- WATER LINE

Scale: 1:100 Date: \_\_\_\_\_

Owner: *Gomathylingam*

Job Title: **PROPOSED RESIDENCES AT PLOT NO: B270 DOOR NO: 48 10TH AVENUE ASHOK NAGAR MADRAS - 63 BEARING T.S NO: 55 IN BLOCK NO: 58 FOR MRS. GOMATHYLINGAM**

Architect: *S. Subramanian* M. Arch, A.I.A.  
Architect & Interior Designer  
Licensed Class I Surveyor No. 90  
87 Vidyaranya II Main Road  
Kasturibai Nagar, Adyar  
Madras - 600 020. Ph: 411305

Planning Permit No. *A/150/92*

**APPROVED**

SUBJECT TO THE CONDITIONS IN THIS ORDER.

No. *A/150/92* of *09/92*

*Ok* *30/9/92*

FOR MEMBER SECRETARY  
MADRAS METROPOLITAN  
DEVELOPMENT AUTHORITY  
MADRAS - 600 008.

Plot area =  $29.47 \times 12573 = 370,500$  sqm

Area of building =  $(21.946 \times 12.573) = 275,500$  sqm

Area of terrace =  $(10.511 \times 1,371) = 14,400$  sqm

Area of open terrace =  $607.95$  sqm

Area of first floor =  $274.25$  sqm

Area of mezzanine floor =  $58.43$  sqm

Area of ground floor =  $267.73$  sqm

Area of terrace floor plan =  $575.20$  sqm

Area of open terrace =  $406.50$  sqm