

SIDE ELEVATION. Planning Permit No. A/2009/92

SECTION ON 'AB'.

APPROVED
 SUBJECT TO THE CONDITIONS IN THIS OFFICE LETTER.
 No. A1/22272/92 Date 12-8-92
 FOR MEMBER SECRETARY
 MADRAS METROPOLITAN
 DEVELOPMENT AUTHORITY
 MADRAS - 600 008

CONCRETE IN CM 1:5:10 FOR FOUNDATION.
 BRICK WORK IN FOUNDATION, BASEMENT & SUPER STRUCTURE IN CM 1:6.
 FLOORING IN BLUE METAL CONCRETE IN CM 1:5:10 & FINISH WITH MOSAICTILES.
 PLINTH BEAM, ROOF SLAB, LINTEL & SUN SHADE IN RCC 1:2:4.
 PLASTERING IN CM 1:4 - 1/2" TK.
 DOOR: D: 3'-3" x 6'-6" (1.00 x 2.00); D₁: 2'-6" x 6'-6" (.75 x 2.00).
 WINDOW: W: 3'-0" x 4'-0" (0.90 x 1.20); VENTILATOR: V: 3'-0" x 2'-0" (0.90 x 0.60).

SECTION OF WELL.
 SECTION OF SEPTIC TANK.

SITE AREA : 1214.75 SQ. FT. 112.85 SQ. MTS.
 BUILDING " : 560.50 " 52.07 "
 OPEN SPACE : 654.25 " 60.78 "

Plan showing the proposed construction of a dwelling at plot no. 11, in S.No. 17 part, of Kodungaiyur village, Division no. 1. Corporation of Madras.
 SCALE: 1" = 8'-0" (1:100).

GF = 41'6" x 14'9" = 612.284 sq ft = 56.88 m²
 FSI = 56.88 / 112.39 = 0.50,
 Coverage = 56.88 / 112.39 x 100 = 50%

SCRUTINY PLAN
A1/22272/92
 28/10/92
 SITE BOUNDARY: [Symbol]
 EXISTING ROADS: [Symbol]
 PRO. WORKS: [Symbol]

V. Balasubramani
 V. BALASUBRAMANI, B. Arch., M.C.A.,
 ARCHITECT
 Licenced Surveyor Regd. No. R. A. 161
 CORPORATION OF MADRAS
 No. 3, Paper Mills Road, First Floor,
 NEAR PERAMBUR CHURCH MADRAS-600 014

Hernandez
 OWNER.

GROUND FLOOR PLAN.