



LEGEND		
CODE	SIZE	DESCRIPTION
FD	2.44 x 2.18	COUNTRY WOOD FRAMED FRENCH DOOR
D1	1.00 x 2.18	TEAK WOOD FRAMED FLUSH DOOR
D2	0.91 x 2.18	COUNTRY WOOD FRAMED FLUSH DOOR
D3	0.76 x 2.18	COUNTRY WOOD FRAMED FLUSH DOOR
W5	1.475 x 1.370	STEEL GLAZED WINDOW
W6	1.475 x 0.875	STEEL GLAZED WINDOW
W7	1.175 x 1.370	STEEL GLAZED WINDOW
W9	0.975 x 1.370	STEEL GLAZED WINDOW
EW1	2.56 x 1.77	STEEL GLAZED BAY WINDOW
V1	0.81 x 0.66	STEEL GLAZED VENTILATOR
V2	0.81 x 0.94	STEEL GLAZED VENTILATOR
J	1.00 x 1.22	OPENING
BW2	0.45 x 1.97	STEEL GLAZED BAY WINDOW
SW1	1.66 x 1.17	ALUMINIUM SLIDING WINDOW
SW2	2.82 x 1.37	DO
SW3	2.76 x 1.37	DO

SPECIFICATION	
SLNO	DESCRIPTION
1.	P.C.C. 1:4:8 IN FOUNDATION
2.	SAND FILLING IN FOUNDATION
3.	BRICK WORK IN C.M. 1:6
4.	R.C.C. WORK FOR SLABS, LINTELS & BEAMS Etc.,
5.	PLASTERING IN C.M. 1:5 EXTERNAL & 1:4 INTERNAL
6.	MOSAIC TILED FLOORING.
7.	WEATHERING COURSE OF BRICK JELLY LIME CONC.

AREA STATEMENT	
PLOT AREA	815.50 M ²
BUILT UP AREA	1221.8128 M ²

COLOUR INDEX	
PROPOSED CONSTRUCTION	
BOUNDARY OF SITE	
ROAD	

R.No	DATE	REVISIONS	INITIAL

1811	181B	20-9-93	1:100	5-43HOOR	S.M. Srinivasan	
DRG No.	DATE	SCALE	FILE	DRAWN	CHECKED	

PROPOSED CONSTRUCTION OF FLATS AT DOOR No: 5, IV MAIN ROAD, GANDHINAGAR, ADAYAR, MADRAS - 600 020
 PLOT No: 170, T.S.No:16. URUR VILLAGE, BLOCK No:1
 TALUK: MYLAPORE TRIPLICANE CORP.DIV.No:151 OLD No: 137
 CIRCLE : 10

OWNER'S SIGNATURE *S. Rajam*

[Signature]
 P.K. SUBRAMANIAN
 B.E., M.E. (P.W.)
 Chartered Civil Engineer
 Licensed Surveyor - Class

LICENSED SURVEYOR L.No: 306 - 93 / 94.

