



APPROVED
 SUBJECT TO THE CONDITIONS IN
 THIS OFFICE LETTER.
 Planning Permit No. 16702/269/83
 No. 3788/93 Date 07-93

SCHEDULE OF JOINERY

TYPE	DETAIL	WIDTH	HEIGHT
D1	T/W PANELLLED DOOR	314	2133
D2	T/W PANELLLED DOOR	764	2133
W1	T/W GLAZED WINDOW	1825	1818
W2	T/W GLAZED WINDOW	1818	1818
W3	T/W GLAZED WINDOW	1211	1818
BW1	BAY WINDOW	1818	1524
V1	T/W GLAZED VENTILATOR	610	610
V2	T/W GLAZED VENTILATOR	381	610

SPECIFICATION

FOUNDATION: BRICK WORK FOOTING
 SUPER STRUCTURE: BRICK WORK IN CM. 1:6
 R.C.C.: ALL R.C.C. ITEMS 1:2:4 MIX WITH NECESSARY STEEL REINFORCEMENT
 PLASTERING: FOR WALLS IN CM. 1:4 FOR CEILING IN CM. 1:3
 WOOD WORK: ALL WOOD WORK IN BEST QUALITY TEAKWOOD
 PAINTING: PAINTING WITH CEMENT PAINT

COLOUR INDEX

- PROPOSED
- ROAD
- BOUNDARY

AREA STATEMENT

TOTAL SITE EXTENT	445.934
GROUND FLOOR	259.165
FIRST FLOOR	266.1095
TOTAL BUILT UP AREA	525.6
GROUND COVERAGE	59.8%

F.S.I - 1.18

PROPOSED BUILDING AT
 DOOR NO. 47 HOSPITAL ROAD
 SAIDAPET MADRAS. 15 IN
 S.NO. 59/4 PT. (T.S.NO.83
 BLOCK NO.17) SAIDAPET VILLAGE.

SCALE 1:100
 DATE: 2.06.93
 DRAWN: K. PANDU

OWNERS SIGNATURE
 Mrs. Jayalakshmi Linga

ARCHITECT:
 W. ANAND
 COUNCIL REG. NO. CA/88/11631
 R.A. NO. IN CORPORATION - 177
 9, SECOND MAIN ROAD, GANDHI NAGAR
 ADYAR, MADRAS 600 020. MCA No. CA/88/11631
 8, II MAIN ROAD, GANDHI NAGAR
 ADYAR, MADRAS-600 020