



PROPOSED BUILDING AT D.No 9 MANDHAVELI ST MANDHAVELI-PARLAM. MYLAPORE VILLAGE OF T.S.No. 4436/782/1993 No. 98

FOR MR. A. MAHMOOD

SCHEDULE OF AREA

M/D TH FRAMED MAIN DOOR	3'3" x 7'0"	99 x 213
D. TH FRAMED DOOR	3'0" x 7'0"	91 x 213
D. "	2'6" x 7'0"	76 x 213
W. ALU GLAZED WINDOW	6'0" x 4'6"	182 x 137
W. "	5'0" x 4'6"	152 x 137
K.W. ALU KITCHEN WINDOW	5'0" x 3'6"	152 x 106
V. ALU GLAZED VENTILATOR	3'0" x 2'0"	91 x 61
SW. SPECIAL WINDOW	6'0" x 5'0"	244 x 152

SPECIFICATIONS

FOUNDATION: R.C.C. COLUMN FOUNDATION 1:2:4

SUPER STRUCTURE: BRICK WORK IN C.M. 1:2:4

ROOFING: 1/2" THK R.C.C. SLAB IN 1:2:4 MK

PLASTERING: IN CEMENT MORTAR 1:5

FLOORING: MOSAIC FLOOR WITH C.M. 1:4

WOOD WORK: O. TEAK WOOD AND ALL

VENTILATORS ARE MADE BY ALUMINUM.

AREA STATEMENT

	SFT	SOM
PLOT AREA	6090.00	62174
GROUND FLOOR	1517.00	140.98
FIRST FLOOR	2831.00	263.10
SECOND FLOOR	2831.00	263.10
THIRD FLOOR	2831.00	263.10
TOTAL FLOOR	10010.00	930.29
PLOT COVERAGE	37%	
F.S.I	10.010/6090 = 1.496	
NON F.S.I. AREA	978/10.010 x 100 = 9.77%	

COLOUR INDEX

- - PROPOSED
- - ROAD
- - SITE BOUNDARY
- - SEWER LINE

SCALE 1:8'0" 1:100 DATE

SIGNATURE OF OWNER

SIGNATURE OF LICENSED SURVEYOR

MAHMOOD AT. 10/11/93
MEMBER COUNCIL OF ARCHITECTURE
G. A. 80/5747.

Planning Permit No. 10742/303
APPROVED
SUBJECT TO THE CONDITIONS IN THIS OFFICE LETTER.
No. 7950/93
08-93

FOR MEMBER SECRETARY
MADRAS METROPOLITAN
DEVELOPMENT AUTHORITY
MADRAS - 600 008.

Proposal not commenced

Proposed buildings

This site has to be demolished

Application not sanctioned

Danglishan plan

2824/1700

29.1.89