



- REFERENCE**
- PROPOSED CONSTRUCTION
  - BOUNDARY LINE
  - ROAD
  - SEWAGE LINE
- SPECIFICATIONS**
1. ALL FOUNDATION CONCRETE WILL BE CEMENT CONCRETE OF 1:5:10 USING 40MM GAUGE HAND BROKEN STONE JELLY
  2. LEVELLING COURSE WILL BE CEMENT CONCRETE OF 1:5:10 USING 40MM GAUGE OF 4 1/2" THICKNESS
  3. ALL BRICKWORK IN FOUNDATION AND BASEMENT WILL BE OF CEMENT MORTAR 1:5 USING I CLASS CHAMBER BURNT BRICKS OF SIZE 9"x4 1/2"x3"
  4. ALL R.C.C WORK WILL BE OF MIX 1:2:4 USING 10MM TO 20MM HAND BROKEN GRANITE STONE JELLY WITH REINFORCEMENT.
  5. ALL ROOF SLAB TO HAVE WEATHERING COURSE IN BRICK JELLY OF SIZE 20MM GAUGE IN PURE SLACKED LIME (NO SAND) PROPORTION OF JELLY LIME BEING 32:12 1/2.
  6. CEMENT PLASTER FOR NEW WILL BE OF 20MM THICK INSIDE AND 12MM THICKNESS OUTSIDE IN C.M 1:5
  7. ALL WOOD WORK WILL BE BEST SEASONED.

**AREA STATEMENT**

	Sq. FT	Sq. M.
TOTAL PLOT EXTENT	7200	668.90
GROUND FLOOR	947.13	87.99
TOTAL PLINTH AREA	947.13	87.99

**SCHEDULE OF JOINERY**

EXISTING			
TYPE	DESCRIPTION	FEET	METRIC
D	DOOR	3'-0" x 7'-0"	0.91 x 2.13
D1	- DO -	2'-9" x 7'-0"	0.84 x 2.13
D2	- DO -	2'-6" x 7'-0"	0.76 x 2.13
W	WINDOW	6'-0" x 4'-6"	1.83 x 1.37
W2	- DO -	3'-0" x 4'-6"	0.91 x 1.37
W3	- DO -	2'-6" x 4'-6"	0.76 x 1.37
J	JALLY	2'-6" x 2'-0"	0.76 x 0.61

**PROPOSED**

V	VENTILATOR	2'-0" x 2'-0"	0.61 x 0.61
---	------------	---------------	-------------

**PROPOSED ADDITIONAL TOILET FOR M. MALARVIZHI AT SURVEY NO. 16 PART, PLOT NO. 28, NADUVAK-KARAI MADRAS DISTRICT**

SCALE : 1" = 8'-0" (1:100) JOB NO : 1474/94  
DATE : 14-11-94 DRG NO : 1  
DEALT BY : B.S.M. DRAWN BY : S. NIVYALAKSHMI

**APPLICANT**  
M. Malavizhi

**LICENSED SURVEYOR**  
R. A. NO 151

**PLANNING AND DESIGN GROUP**  
**PADGRO**  
CONSULTANTS PRIVATE LIMITED  
ARCHITECTS AND TOWN PLANNERS  
25A LADYMAHAVAN NAIR ROAD  
MAHALINGAPURAM MADRAS-34  
PHONE : 8254026