



TYPE	DETAIL	WIDTH	HEIGHT
D	C.M. PANELLED DOOR	1000	2134
D1	DOOR Revised Plan 9/15	915	2134
D2	DOOR 2099, 782	782	2134
W	C.W. GLAZED WINDOW	2438	1524
W1	-DO-	1829	1524
W2	-DO-	1219	1524
W3	-DO-	1219	1219
W4	DOOR	1219	1524
V	C.W. GLAZED VENTILATOR	750	610
WR	WARDROBE		

**SPECIFICATION:**

FOUNDATION : R.C.C. COLUMN FOOTINGS  
 BRICK WORK : CHAFF FOR SUPER STRUCTURE  
 PLASTERING : C.M. 1:3 FOR WALLS & 1:3 FOR CEILING  
 FLOORING : MOSAIC FLOORING  
 CEMENT PAINT : 2 COAT FOR WALLS & 1 EXTRA COAT FOR CEILING  
 R.C.C. : 1:2:4 FOR SLABS & LINTELS  
 WOOD WORK : ALL WOOD WORKS IN BEST QUALITY TIMBER  
 WEATHERING : BUJELLY LIME MORTAR OVER ROOF  
 COURSE : SLAB ONE LAYER OF COUNTRY TILES  
 L.W.C. : FLOOR HT. 900 mm ABOVE ROAD LVL.

**COLOUR INDEX:**

PROPOSED ROAD BOUNDARY

	SQ. M
TOTAL SITE EXTENT:	736.80
GROUND FLOOR	284.84
FIRST FLOOR	292.35
SECOND FLOOR	297.63
THIRD FLOOR	297.63
DEDUCTION FOR WATCHMAN, PUMP, ELECTRICAL & STORE ROOM	(-89.10)
<b>TOTAL BUILT UP</b>	<b>1103.44</b>
<b>GROUND COVERAGE</b>	<b>40.39%</b>
<b>F.S.I</b>	<b>1.497</b>

**PROPOSED BUILDING**  
 AT DOOR NO. 11,  
 THEYAGARAJA GRAMNI ROAD,  
 T.S.NO: 6812,  
 BLOCK NO : 106  
 T.NAGAR,  
 MADRAS

SCALE [1:100]  
 DATE: 08-10-94  
 DRAWN: K.K.SAJAN

SIGNATURE OF OWNER  
*M. Suresh Kumar*

ARCHITECT  
**W. ANAND**  
 COUNCIL REG. NO: CA/88/11631  
 R.A.NO IN CORPORATION - 177  
 8, SECOND MAIN ROAD, GANDHI NAGAR,  
 ADYAR, MADRAS - 600 020.  
 PH: 418241

