



SAND FILLING FOR FOUNDATION 153 MM THICK
 BASE CONC. FOR FOUNDATION INC. C-1:2:4. 305MM/153MM THICK
 R.C.C. COLUMN FOUNDATION IN C.C. 1:2:4. 46" x 46"
 R.C.C. COLUMN INC. C-1:2:4. 0'9" x 0'9"
 R.C.C. TIE & ROOF BEAMS INC. C-1:2:4. 0'5" x 1'0" / 0'9" x 1'6"
 R.C.C. ROOF SLAB & LINTELS INC. C-1:2:4. 127 MM THICK
 R.C.C. SUNSHADE IN C.C. 1:2:4. 60 MM THICK
 BRICK WORK IN CEMENT MORTAR 1:5. 0'9" THICK
 PLASTERING WITH CEMENT MORTAR 1:4. 12 MM THICK
 FLOORING WITH MORIC TILES OVER B.J.C.
 WEATHERING COURSE WITH TWO COURSE OF FLAT TILES.

P.	T.W. DOOR	3'3" x 7'0"	991 x 2134
P1	DO.	3'0" x 7'0"	914 x 2134
P2	DO.	2'6" x 7'0"	762 x 2134
V.	T.W. WINDOW	5'0" x 5'0"	1524 x 1524
V1	DO.	4'0" x 5'0"	1219 x 1524
V.	VENTILATOR	3'0" x 1'6"	914 x 457
J.	JOLLY WORK	5'0" x 5'0"	1524 x 1524
G.	GATE	12'0" x 4'6"	3658 x 1372

TOTAL PLOT AREA	3375.54 SQ. FT. (313.54 M ²)
GROUND FLOOR	1403.34 SQ. FT. (130.34 M ²)
FIRST FLOOR	1305.94 SQ. FT. (121.23 M ²)
SECOND FLOOR	1066.26 SQ. FT. (98.47 M ²)
COVERAGE	41.62%
F.S.I.	1.12

PROPOSED WORK	▬▬▬	ROAD PORTION	▬▬▬
EXISTING WORK	▬▬▬	SITE BOUNDARY	▬▬▬
TO BE REMOVED	▬▬▬		

PLAN SHOWING THE PROPOSED ADDITIONS OF THE DWELLING HOUSE AT PLOT NO. 2217, M. BLOCK A.E. BLOCK 7TH ST. A.A. NAGAR. DIVISION : 64.
 SCALE 1" = 8'0" SANCTIONED B.A. : 643/83 dt 6-7-83.

