



**SCHEDULE OF JOINERY:**

TYPE	DETAIL	WIDTH	HEIGHT
D	C.W. PANELLED DOOR	1000	2135
D1	-DO-	815	2135
D2	-DO-	762	2135
D3	-DO-	688	2135
PD	POOJA DOOR	914	2135
W	C.W. GLAZED WINDOW	1830	1372
FW	C.W. GLAZED WINDOW	1219	1830
W1	-DO-	1219	1372
W2	-DO-	1219	1067
WB	WARDROBE		
V	C.W. GLAZED VENTILATOR	810	915

**SPECIFICATION:**

FOUNDATION : R.C.C COLUMN FOOTINGS  
 BRICK WORK : C.M 1:8 FOR SUPER STRUCTURE  
 PLASTERING : C.M 1:5 FOR WALLS & 1:3 FOR CEILING  
 FLOORING : MOSAIC FLOORING  
 CEMENT PAINT : 2,COAT FOR WALLS & 1,EXTRA COAT FOR CEILING  
 R.C.C : 1:2:4 FOR SLABS & LINTELS  
 WOOD WORK : ALL WOOD WORKS IN BEST QUALITY TIMBER  
 WEATHERING : BUJELLY LIME MORTAR OVER ROOF  
 COURSE : SLAB ONE LAYER OF COUNTRY TILES

**COLOUR INDEX:**

PROPOSED ROAD BOUNDARY

**AREA STATEMENT SQ. M**

TOTAL SITE EXTENT:	434.00
GROUND FLOOR	162.56
FIRST FLOOR	172.40
SECOND FLOOR	163.54
THIRD FLOOR	155.37
DEDUCTION FOR PUMP & ELECTRICAL ROOM	(-6.89)
TOTAL BUILTUP AREA	647.18
GROUND COVERAGE:	39.72 %
F.S.I	1.49

PROPOSED BUILDING AT DOOR NO:13, POSTAL COLONY, 11th MAIN ROAD, WEST MAMBALAM, MADRAS-33. T.S.NO:11, BLOCK NO:59, KODAMBAKKAM VILLAGE.

SCALE [1:100]  
 DATE: 03-08-95  
 DRAWN: SAJAN

SIGNATURE OF POWER OF ATTORNEY  
 P. BHAVANI

ARCHITECT  
**W. ANAND**  
 COUNCIL REG. NO:CA/88/11631  
 R.A.IN IN CORPORATION - 177  
 #2, 4TH CROSS STREET, SEETHAMMAL COLONY,  
 ALWARPET, MADRAS - 600 018  
 TEL: 433070

