



APPROVED
 SUBJECT TO THE CONDITIONS IN THIS SECTION [X.X]
 No. B. 2228/75 Date: 3-9-75
 FOR MEMBER SECRETARY
 MADRAS METROPOLITAN
 DEVELOPMENT AUTHORITY
 MADRAS - 600 008.

SLV
D.V.
W.S.V.
Road - Tarrad
Eng. bly. not yet developed
Inspection plan
 7/11/94

SCHEDULE OF JOINERY:

TYPE	DETAIL	WIDTH	HEIGHT
D	C.W. UNGLAZED DOOR	914	2134
D1	-DO-	782	2134
D2	-DO-	686	2134
W	C.W. GLAZED WINDOW	1791	1219
W1	-DO-	1219	1219
W1	-DO-	1219	914
W1	-DO-	610	1219
V	C.W. GLAZED VENTILATOR	610	914
WR	WARDROBE		

SPECIFICATION: B. 2254/74

FOUNDATION: R.C.C. COLUMN FOOTINGS
 BRICK WORK: C.M. 1:6 FOR SUPER STRUCTURE
 PLASTERING: C.M. 1:5 FOR WALLS & 1:3 FOR CEILING
 FLOORING: MOSAIC FLOORING
 CEMENT PAINT: COAT FOR WALLS & 1 EXTRA COAT FOR CEILING
 R.C.C: 1:2:4 FOR SLABS & LINTELS
 WOOD WORK: ALL WOOD WORKS IN BEST QUALITY TIMBER
 WEATHERING: BUJALLY LIME MORTAR OVER ROOF
 COURSE: SLAB ONE LAYER OF COUNTRY TILES
 I.W.C: FLOOR HEIGHT OF I.W.C. 900MM ABOVE FINISH

COLOUR INDEX:

PROPOSED	ROAD	BOUNDARY

AREA STATEMENT SQ. M

TOTAL SITE EXTENT:	446.00
GROUND FLOOR	165.45
FIRST FLOOR	168.62
SECOND FLOOR	168.62
THIRD FLOOR	168.62
DEDUCTION FOR WATCHMAN ROOM (-11.45)	
TOTAL BUILTUP AREA	659.83
GROUND COVERAGE:	37.8 %
F.S.I	1.479

PROPOSED BUILDING AT
 T.S.NO: 70, BLOCK NO:41
 KODAMBAKKAM VILLAGE
 DOOR NO: 24
 RAMAKRISHNAPURAM IIIRD ST.
 WEST MAMBALAM,
 MADRAS - 600 033.

	SCALE	DATE:
	[1:100]	28-09-84
SIGNATURE OF POWER OF ATTORNEY	DRAWN: SAJAN.	

ARCHITECT
W. ANAND

COUNCIL REG. NO: CA/88/11831
 R.A.NO IN CORPORATION - 177
 6, SECOND MAIN ROAD, GANDHI NAGAR,
 MADRAS - 600 033.

