



1. SAND FILLING IN FOUNDATION BASE
2. P.C.C. 1:1.5:10 USING 40 MM METALS
3. R.C.C. 1:2:4 USING 20MM METALS
4. B.W. IN C.M. 1:1.5
5. PLASTERING WALL IN C.M. 1:1.5
6. PLASTERING CEILING C.M. 1:1.5
7. USE SOLING COURSE 200 TK.
8. ROOFING WITH A.C. SHEET FOR WARE HOUSE
9. FLOORING WITH GRANOLITHIC FOR WARE HOUSE AND MOSAIC FLOORING FOR OFFICE BUILDING AND SECURITY BUNK

1. RS ROLLING SHUTTER 3000x3000
2. DOOR - D. - 900 x 2100
3. DOOR - D. - 750 x 2100
4. WINDOW - W. - 1500 x 1270
5. VENTILATOR - V. - 1500 x 300
6. VENTILATOR - V. - 700 x 600

OWNER  
Partner  
INDIA SHOES

COLOUR REFERENCE  
PROPOSED BOUNDARY  
EXISTING ROAD

PROPOSED WARE HOUSE AT  
MOUNT-POONAMALLEE ROAD  
PORUR VILLAGE, S.No 51/1A2A

AREA PARTICULARS

PLOT AREA	1903.34m <sup>2</sup>
PRO. WARE HOUSE	784.16m <sup>2</sup>
PRO. OFFICE BUILDING	32.73m <sup>2</sup>
PRO. SECURITY BUNK	11.93m <sup>2</sup>
TOTAL AREA:	829.66m <sup>2</sup>

LORRY PARKING REQUIRED - 4 Nos.  
LORRY PARKING PROVIDED - 4 Nos.

SURVEYOR  
R. Mohan Rao, D.C.E.,  
LICENSED SURVEYOR  
Corporation of Madras  
REG. NO. 14  
AMBATTUR TOWN SHIP  
ALANKUR MUNICIPALITY  
Consulting Engineer  
Office: No. 1, Madhav Road,  
T. NAGAR, MADRAS - 600 017.