



Planning Permit No. A/2406/2/92  
**APPROVED**  
 SUBJECT TO THE CONDITIONS IN  
 THIS OFFICE LETTER.  
 No. A/2406/2/92, Date: 7-1-92  
 FOR MEMBER SECRETARY  
 MADRAS METROPOLITAN  
 DEVELOPMENT AUTHORITY  
 MADRAS

LEGEND		
CODE	SIZE	DESCRIPTION
F03	1.83 x 1.981	COUNTRY WOOD FRAMED FRENCH DOOR (parted)
D	1.22 x 1.981	TEAK WOOD FRAMED FLUSH DOOR
D2	0.91 x 1.981	COUNTRY WOOD FRAMED FLUSH DOOR
D3	0.76 x 1.981	COUNTRY WOOD FRAMED FLUSH DOOR
W5	1.475 x 1.37	STEEL GLAZED WINDOW
W7	1.175 x 1.37	STEEL GLAZED WINDOW
W9	0.975 x 1.37	STEEL GLAZED WINDOW
V2	0.81 x 0.94	STEEL GLAZED VENTILATOR
O	1.98 x 1.07	OPENING

SPECIFICATION	
SLNO	DESCRIPTION
1.	P.C.C. 1:4:8 IN FOUNDATION
2.	SAND FILLING IN FOUNDATION
3.	BRICK WORK IN C.M. 1:6
4.	R.C.C. WORK FOR SLABS, LINTELS & BEAMS Etc.,
5.	PLASTERING IN C.M. 1:5 EXTERNAL & 1:4 INTERNAL
6.	MOSAIC TILED FLOORING.
7.	WEATHERING COURSE OF BRICK JELLY LIME CONC.

AREA STATEMENT	
PLOT AREA	275.27 SQ.M
BUILT UP AREA	334.3186 SQ.M

COLOUR INDEX			
PROPOSED CONSTRUCTION	BOUNDARY OF SITE	ROAD	

R.No	DATE	REVISIONS	INITIAL

DRG No:	DATE	SCALE	FILE	DRAWN	CHECKED
1 193 179 M	17-02-94	1 : 100	SPIC 2ACOR4	Jones	19/10/96

PROPOSED CONSTRUCTION OF DWELLING UNITS IN PLOT No : 4, L.A. No 3/95 DTD 5.6.95 AT SURVEY Nos. 249/3, 250/2, 250/3, 251/5, 254/4 & 328/1, (VILLAGE - VELACHERY VELACHERY, TAMBARAM ROAD MADRAS - 600 042. TALUK : MAMBALAM - GUINDY, CORP. DIV. NO: 153 ZONE : X

OWNER'S SIGNATURE  
 LICENSED SURVEYOR  
 L.S. No : 306 98/97