



PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING IN S.NO 916/2, PART NO:54, AT KORATTUR VILLAGE, SAIDAPET TALUK, CHENGALPAT DISTRICT.

SCALE=1:100

For scrutiny plan.
 4/13/97

SPECIFICATION

FOUNDATION COLUMN FOUNDATION
 SUPER STRUCTURE 9"TK BRICK WK IN CM 1:4
 4 1/2"TK BRICK WK IN CM 1:3
 PLINTH BEAM RCC COLUMN LINTEL SUNSHADE
 R.C.C 1:2:4 ROOF SLAB
 FLOOR FINISHED WITH MOSAIC TILES
 INTERNAL EXTERNAL PLASTERING IN CM 1:5
 WEATHERING COURSE BRICK JELLY CONCRETE WITH PRESSED TILES.
 ELECTRIFICATION WORK WITH CONCEALED WIRING.

JOINERY DETAIL

D	DOOR	3'-3" x 7'-0"
D1		3'-0" x 7'-0"
D2		2'-6" x 7'-0"
W	WINDOW	5'-0" x 4'-6"
W1		4'-0" x 4'-6"
W2		4'-0" x 4'-6"
V	VENTILATOR	2'-0" x 2'-0"

AREA DETAIL

PLOT EXTENT	675.0 SQ.FT	62.73 SQM
PROPOSED G. FLOOR	353.0 "	32.68 "
PLOT COVERAGE	52%	
F.S.I	0.52	

SIGN OF OWNER

(Signature)

SIGN OF L.SURVEYOR

(Signature)
 M. MOHAN
 LICENCED SURVEYOR
 CORPORATION OF MADRAS,
 AVADI, AMBATTUR TOWN SHIP,
 ANNA NAGAR PLAZA, SHOP NO. 16, 1st FLOOR,
 C-47, Hind Avenue, MADRAS-40 (T.N.H.B.)

