



A/28199/21/98
APPROVED
 SUBJECT TO THE CONDITIONS OF THE
 PLAN OF USE OFFERED
 A/21685/97
 02.98
 O/C [Signature]
 FOR MEMBER SECRETARY
 CHENNAI METROPOLITAN
 DEVELOPMENT AUTHORITY
 CHENNAI - 600 032

PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING AT PLOT NO: 22, R S NO: 320, T.D. NO 110 PADASALAI STREET LAKSHMIPURAM CHROMPET THIRUNEERMALAI SAIDAPET TALUK CHENGALPUT DISTRICT

SPECIFICATION	JOINERY
FOUNDATION With pcc 1:2:4 with sand	MD Main Door 1067 x 2134
FLOORING Floor finish over pcc 1:4:8 with sand	D Door 914 x 2134
S STRUCTURE Brick work in cm 1:5	Di Door 762 x 2134
ROOFING Roof slab rcc 1:2:4	W Window 2436 x 1372
W COURSE 2 layer of pressed tiles over brick jelly with cm	Wi Window 1829 x 1372
JOINERY With best indian teak wood	Wl Window 1219 x 1372
	KW Kitchen window 1829 x 1067
	V VENTILATOR 914 x 610
	Vi VENTILATOR 762 x 610

AREA STATEMENT	COLOR INDEX
PLOT EXTENT 5336 S.F.	PROPOSED COLOR ○
GROUND FLOOR AREA 3071	ROAD COLOR ○
FIRST FLOOR AREA 3450	SITE COLOR ○
TOTAL AREA 6521	
PLOT COVERAGE 61.11%	
F.S.I 1.21	

OWNER

K. Subramanyam
 K. SUBRAMANYAM.
 R.A. NO. 296,
 CORPORATION OF MACRAS.
 LICENCED SURVEYOR

SCALE 1" = 8' 0"
 DATE 2.7.97

architects

SRINIVASA ENTERPRISES
 74 BAZULLAH ROAD
 T NAGAR
 CHENNAI 17

FOR MR R EARNEST (PA HOLDER)