



A/24218/158/97
 Planning Permit No.
APPROVED
 SUBJECT TO THE CONDITIONS IN THIS OFFICE ETTER.
 No. 1305/97 Date 1.4.97
 FOR MEMBER SECRETARY
 MADRAS METROPOLITAN
 DEVELOPMENT AUTHORITY
 MADRAS - 600 008.

SCHEDULE OF JOINERY			
TYPE	DESCRIPTION	WIDTH	HEIGHT
D	T.W. PANNELED DOOR	4'0"	7'0"
D1	T.W. FLUSH DOOR	3'0"	7'0"
D2	-do-	2'6"	7'0"
W	T.W. GLAZED WINDOW	8'0"	6'0"
W1	-do-	6'0"	4'6"
W2	-do-	7'0"	4'6"
W3	-do-	2'0"	4'6"
V	T.W. LOWERED VENTILATOR	2'0"	4'6"

- SPECIFICATIONS**
- FOUNDATION R.C.C. FOOTING WITH COLUMN 1:2:4
 - BRICKWORK IN SUPERSTRUCTURE AND PARAPET WALL IN CM 1:3
 - R.C.C. IN 1:2:4 FOR ROOF SLAB, BEAMS, LINTES & SUNSHADES ETC.
 - PLASTERING IN CM 1:4
 - ALL WOODWORK IN T.W.
 - FLOORING MOSAIC
 - TWO COATS OF PAINT OVER ONE COAT OF PRIMER
 - TWO COATS OF COLOUR WASH OVER ONE COAT OF WHITE COAT.
 - WEATHERING COURSE LAID IN CM 1:3 WITH TWO COATS OF FLAT TILES IN SLOPE.

AREA STATEMENT		
PLOT AREA	10,900 SFT	1019.11 SQM
GROUND FLOOR	940 SFT	87.26 SQM
FIRST FLOOR	559.25 SFT	51.58 SQM
TOTAL BUILT UP AREA	1499.25 SFT	138.84 SQM
F.S.I. 0.13	COVERAGE : 9%	

Plan showing the proposed construction at GRAMANATHAM s.no: 439 3B of Solinganallur village, Saidapet taluk, ANNA district.

scale: 1:100

OWNER'S SIGNATURE
D. Kousalya
 D. KOUSALYA

SIGNATURE AND SEAL OF LICENSED SURVEYOR.
K. SUNDARARAJAN, S.C.
 LICENSED SURVEYOR
 TAMBARAM MUNICIPALITY
 OFF. NO. 20, SHANMUGAM ROAD
 WEST TAMBARAM, MADRAS - 600 045