



CMDA (B) I.P.P. No. B2/2803/97
 C.No. B2/2803/97
 P.A. B1/12/97
 A.P. 17/197

Planning Permit No. B/24837/287/97
APPROVED
 SUBJECT TO THE CHENNAI MUNICIPAL CORPORATION DEVELOPMENT AUTHORITY CHENNAI-600 008

PROPOSED RESIDENTIAL BUILDING AT DOOR NO.39 SOUTH SWANKOIL STREET BEARING T.S NO 33, BLOCK NO.3 OF KODAMBAKKAM, VADAPALANI, MADRAS - 600 026

ok

SCHEDULE OF JOINERIES

D DOOR	3'3" x 7'0" 0.99 x 2.13
D1 do	3'0" x 6'0" 0.91 x 1.83
D2 do	2'6" x 6'0" 0.76 x 1.83
W WINDOW	4'6" x 4'6" 1.37 x 1.37
W1 do	3'0" x 4'6" 0.91 x 1.37
W2 do	6'3" x 4'6" 1.90 x 1.37
V VENTILATOR	2'0" x 2'0" 0.61 x 0.61
W4 WINDOW	2'10" x 3'6" 0.68 x 1.06
W4 do	2'10" x 2'6" 0.68 x 0.76
W5 do	2'0" x 3'6" 0.61 x 1.06

- SPECIFICATION**
- 1 THE BUILDING SHALL BE CONSTRUCTED WITH LOAD BEARING 9TK BRICK WORK FOR EXTERIOR AND 4 1/2 TK BRICK PARTITION WALLS FOR INTERIOR SURFACES
 - 2 THE ROOF SLABS SHALL BE IN R.C.C 1:2:4 MIN 4 1/2" THICK
 - 3 ALL EXPOSED CONCRETE SURFACES SHALL BE PLASTERED IN CM 1:3 AND BRICK MASONRY SURFACES IN CM 1:4
 - 4 THE FLOORING SHALL BE LAID WITH HYDRAULICALLY PRESSED CEMENT MOSAIC TILES OF APPROVED COLOUR
 - 5 THE WEATHERING COURSE SHALL BE LAID TO SLOPE IN BRICK JELLY LIME CONCRETE WITH 4TK AND FINISHED WITH ONE LAYER OF COUNTRY TILES

AREA STATEMENT

	SQ. FT.	SQ.M.
PLOT EXTENT	7823.38	727.13
GROUND FLOOR AREA	3756.4377	348.325
FIRST FLOOR AREA	4125.9677	383.454
SECOND FLOOR AREA	3912.6084	365.502
TOTAL	11598.013	1073.682

F.S.I 1:48

COLOUR INDEX

PROPOSED: [Symbol]

ROAD: [Symbol]

BOUNDARY: [Symbol]

SCALE 1"=8'0"

DATE 28-10-1996

SIGNATURE OF OWNER: V.S. Narendran

SIGNATURE OF LICENSED SURVEYOR: S. Senthilkumar

S. SENTHILKUMAR, P.E., R.I.T.E.
 Registered Architect-CA/34/17745
 Council of Architecture
 Licensed Surveyor-R.A. 318
 Corporation of Madras.

NAME AND ADDRESS OF LICENSED SURVEYOR
 S. SENTHILKUMAR BE. A.I.A.
 14, FOURTH MAIN ROAD,
 C. I. T. NAGAR,
 NANDANAM
 MADRAS - 600 035
 Phone 4331255