PLAN SHOWING PROPOS RECONSTRUCTION OF SRI KOTTI SREERAMULU MEMORIAL BUILDING AT PREMISES NO. 126, [illegible] TTAN HIGH ROAD, RSM 1832/30 MYLAPORE, MADRAS. 600 004, CORPORATION OF CHENNAI DIVISION NO. 128, ZONE, NO X

Scale: 1" = 8'-0" 1:100

Proposals ——— Road ———

CMDA 'C'/PP No. C4/3235/88

R.S.A. 24/1/89

D DOOR	4'-0" × 8'0"	122 × 244	
D DOOR	3'-3" × 8'0"	100 × 244	
D2 DOOR	2'-6" × 8'0"	76 × 244	
W window	4'-0" × 5'0"	122 × 152	
J Rec jally	5'-0" × 1'-0"	152 × 305	
V Ventilator	3'-0" × 2'-0"	91 × 61	

A.P. 1/2/61 D.P.

AREA SCHEDULE

plot extent		1975	Sq.ft	188.85	Sq.M
plinth area	GF	641	Sq.ft	59.77	Sq.M
	FF	779	Sq.ft	72.64	Sq.M
	SF	779	Sq.ft	72.64	Sq.M
	TF				
plot coverage				205.05	SQ.M
F.S.I		1:09	TIMES		

Planning Permit No. C/02.5860/8/88

APPROVED

SUBJECT TO THE CONDITIONS IN THIS OFFICE LETTER.

No. C4/3235/88 Date 2-2-89

FOR MEMBER SECRETARY, CHENNAI METROPOLITAN DEVELOPMENT AUTHORITY, CHENNAI-600 008.

KEY PLAN OF SITE

To beach — Kutcheri Road — Road To Trok — To Almarket — Lus church Road — Lus Corner — Ramakrishna Theatre

FRONT ELEVATION.

SECTION ON 'B'

SECTION OF PROP COMP. WALL

DETAILS OF PROP PERCOLATION PIT

GROUND FLOOR & SITE PLAN (SANSKRIT CLASSROOM)

FIRST FLOOR PLAN (YOGA CLASSROOM)

SECOND FLOOR PLAN (TELUGU CLASS ROOM)

TERRACE FLOOR

DETAILS OF STAIR

Rise 7" 1½"
Tread 10"-0"
No of steps
1st flight 5
Landing 6
IInd flight 5
Total 16 No

Executive Engineer, (R & B) TIRU. ATI.