



- SPECIFICATION:-**
- ROOF SLAB IN R.C.C 1:2:4 11cm THICK
 - HOLLOW BLOCK WALL IN CEMENT MORTAR 1:5
 - R.C.C COLUMN IN R.C.C 1:2:4
 - PLINTH BEAM IN R.C.C 1:2:4
 - WALL PLASTERING IN CM 1:5 20 mm THICK
 - CEILING PLASTERING IN CM 1:3 12mm THICK
 - PARAPET WALL IN CM 1:5 1.00M HIGH
 - SILVER GREY MOSAIC FLOOR 22mm THICK
 - T.W. DOOR FRAMES AND FLUSH DOOR SHUTTER
 - ALUMINIUM SLIDING WINDOWS WITH 4mm PLAIN GLASS
 - WEATHERING COURSE - BRICK JELLY CONCRETE LAID WITH PRESSED CLAY TILES.
 - FLOORING CONCRETE IN C.C 1:4:8
 - SAND FILLING
 - R.C.C FOOTING IN R.C.C 1:2:4
 - G.F.L - GROUND FLOOR LEVEL
- JOINERIES:-**
- D1 - DOOR 1.00 x 2.13
 - D2 - DOOR 0.90 x 2.13
 - D3 - DOOR 0.76 x 2.13
 - D4 - DOOR 0.76 x 2.13
 - F/W - FRENCH WINDOW 1.83 x 2.13
 - W1 - WINDOW 1.37 x 1.22
 - W2 - WINDOW 1.37 x 0.91
 - V - VENTILATOR 0.76 x 0.76
 - O - OPENING 0.90 x 2.13
 - J - JALLY 1.37 x 1.22

ALL DIMENSIONS ARE IN "METRES"

AREA STATEMENT:-

PLOT EXTENT	: 605.83 Sq.m
GROUND FLOOR AREA	: 205.05 Sq.m
FIRST FLOOR AREA	: 388.54 Sq.m
SECOND FLOOR AREA	: 143.12 Sq.m
TOTAL BUILT UP AREA	: 736.71 Sq.m
F.S.I PROVIDED	: 1.22
PLOT COVERAGE	: 64.15%
TOTAL NUMBER OF DWELLING	: 4
NUMBER OF CAR PARKING	: 7
CAR PARKING AREA	: 170.09 Sq.m

- REFERENCE:-**
- PROPOSED BUILDING
 - ROAD LIMITS
 - SITE BOUNDARY

M. S. Rajani

POWER AGENT

P.C. GOWRI SHANKAR, B.E.M.I.E.S.I.V.
VALUER & CHARTERED ENGINEER
CLASS-I, LICENSED SURVEYOR
CORPORATION OF CHENNAI-N.Y. 154
8, Vadivelpuram, Chennai-600033.
PH : 489 29 24, 465 14 95

LICENSED SURVEYOR

PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING WITH STILT CAR PARKING AT R.S.No. 84/34, SADHASIVAM STREET, GOPALAPURAM, CHENNAI - 68. (Revision No. 01)

DOOR No :- 14 (Old No.10), Sadhasivam Street VILLAGE :- Mylapore Village

SURVEY No :- R.S. No. 84/34

BLOCK No. :- 4

DIVISION No. :- 60

SCALE :- 1:100

SHEET No. :- 01 OF 01

