



*Re-inspected on 18/12/2001*

*The site ulr is 75m away from C.P. Ramaswamy road and 60m away from B-canal in East. m.s.g. 18/12/2001.*

*Note: The site ulr is far away from B-canal. m.s.g. 24/1/2002*

*Engg corp*

JOINERY DETAILS			
TYPE	DESCRIPTION	WIDTH	HEIGHT
D	C.W. DOOR	99	213
D1	C.W. DOOR	91	213
D2	C.W. DOOR	76	213
W	C.W. WINDOW	183	122
W1	C.W. WINDOW	122	122
W2	C.W. WINDOW	61	122
W3	C.W. WINDOW	91	91
V	C.W. VENTILATOR	45	91

- SPECIFICATIONS:**
- Foundation of plot with 3/5cm thk. with broken granite jelly.
  - C.C. 1:2:4 for all R.C.C. works with broken granite jelly.
  - 23 CM. Brick work in C.M. 1:4
  - 11 CM. Thk. Brick work in C.M. 1:4
  - Plastering the ceiling and exposed concrete surface in C.M. 1:3
  - Plastering the Walls in C.M. 1:4
  - Weathering course in brick jelly lime coat 7.5cm thick with flat tiles set in C.M. 1:3
  - Flooring with hydraulic pressed mosaic tiles set in C.M. 1:4 and skirting 12.5/cm height.
  - The Over Head Tank & Sump is scientifically sealed.

**LEGEND :**

PROPOSED CONSTRUCTION SHOWN THUS

BOUNDARY SHOWN THUS

ROAD SHOWN THUS

SEWER LINE SHOWN THUS

WATER LINE SHOWN THUS

	AREA STATEMENT	
	IN SQ.M.	IN SQ.FT.
STILT FLOOR AREA	15.49	166.75
FIRST FLOOR AREA	122.28	1316.24
SECOND FLOOR AREA	122.28	1316.24
THIRD FLOOR AREA	127.18	1369.05
FOURTH FLOOR AREA	127.18	1369.05
TOTAL FLOOR AREA	514.41	5537.33
PLOT AREA (AS/PATTA)	368.91	3971.00
F.S.I.	1.39	
PLOT COVERAGE	33.15%	

OWNER:

*V. Subramanian*

SCALE: 1:100

DATE: 30.09.2000

JOB NO: 214-00

ALL DIMENSIONS ARE IN CENTIMETRES

JOB TITLE :

PROPOSED APARTMENTS AT OLD DOOR NO:72, NEW DOOR NO:94, DR. RANGA ROAD ABHIRAMAPURAM, CHENNAI-18. BEARING R.S NO:3629/6 FOR MR. S.VENGITARAMAN & MR. V.SUBRAMANIAN

LICENSED SURVEYOR :

*S. Srinivasa*

ARCHITECT AND INTERIOR DESIGNER

S. Srinivasa  
1/2 Main Road  
Kasturba Nagar  
Adyar, Madras-600 022



