

No	Wide	Height	Description
D1	3.3'	7.0'	C.W. Door
D2	3.0'	7.0'	- Do -
W1	5.0'	7.0'	- Do -
W2	5.0'	4.6'	C.W. Glazed window
W3	3.0'	4.6'	- Do -
W4	3.0'	3.0'	- Do -
W5	3.0'	3.0'	- Do -
FD	6.0'	7.0'	Frame Door
V	2.0'	2.0'	Ventilator

CMDA (B) / NO. 1
No. 22/23/2000

- Special Instructions:
1. P.C. Slab
 2. P.C. Beam
 3. P.C. Column
 4. 115 mm Brick Work in CM 1:4
 5. Plastering the Ceiling in CM 1:4
 6. Plastering the Walls in CM 1:4
 7. Weathering Course in Brick Tilted Concrete with a Course of Flat Tiles
 8. The O.H.T. is Scientifically Closed
 9. The U.G. Sump is Scientifically Closed
 10. All W.C.'s in Ground Floor Piped by 0.31 m. From Ground Level

Area Statement: Sq. Ft Sq. M

Plot Area:	3499.00	323.05
Proposed Construction:		
Gr. Lvl. Staircase Area:	237.56	22.08
First Floor Area:	3486.25	324.00
Second Floor Area:	3486.25	324.00
Third Floor Area:	3486.25	324.00
Fourth Floor Area:	3486.25	324.00
Total Builtup Area:	14122.56	1318.05
F.S.I Applied For:	1.433	
Plot Coverage:	37%	

- Legend:
- Proposed Construction
 - Boundary Line
 - Roads
 - Sewer Line
 - Water Line

Owner: Govt. ...

Job Title: Proposed Apartments at D.No. 6 Sarangapani Street, T. Nagar, Chennai. Bearing Old S.No. 82/1, 82/2 & 82/3 Block No. 108 B. T.S. 6913 T. Nagar, Mambalam - Guindy Taluk, Chennai District.

Scale: 1"=80' Date: 02.06.2000

Licensed Surveyor: V. SRINIVASAN, A.I.A., Registered Architect - CA/96/19755 Licensed Surveyor - Corporation of Chennai R.A. No. 344 South Road, West C.I.T. Nagar Chennai - 600 035. Phone: 433 82 62

