



A/000657/143/2005
 Planning Permit No. _____
APPROVED
 SUBJECT TO THE CONDITIONS IN THIS OFFICE LETTER.
 No. 11/14727/2005-6-01 Date: 1-6-01
 O.P. Poojari (16/10)
 FOR MEMBER SECRETARY
 CHENNAI METROPOLITAN
 DEVELOPMENT AUTHORITY
 CHENNAI - 600 008.

SCHEDULE OF JOINERY

TYPE	DETAIL	SIZE
MD	DOOR	3'-3" x 7'-0"
D	DOOR	3'-0" x 7'-0"
D'	DOOR	2'-8" x 7'-0"
W	WINDOW	5'-0" x 4'-0"
W1	WINDOW	4'-6" x 4'-0"
W2	WINDOW	3'-0" x 4'-0"
V	VENTILATOR	2'-0" x 2'-0"
CJ	CEMENT JOLLY	6'-0" x 20'-0"

SPECIFICATIONS:

FOUNDATION : COLUMN FOOTING
 BRICKWORK : C.M 1:6 FOR SUPER STRUCTURE
 PLASTERING : C.M 1:5 FOR WALLS AND C.M 1:3 FOR CEILING.
 CEMENT PAINT: 2 COATS FOR WALLS AND 1 EXTRA COAT FOR CEILING
 R.C.C : 1:2:4 FOR SLABS AND LINTELS
 WOOD WORK: ALL WOOD WORK IN BEST TIMBER
 WEATHERING : B.JELLY LIME MORTAR OVER ROOF COURSE
 SLAB ONE LAYER OF COUNTRY TILES

COLOUR INDEX:

PROPOSED WORK SHOWN [Symbol]
 ROAD WORK SHOWN [Symbol]
 BOUNDARY LINE SHOWN [Symbol]
 SEWER LINE SHOWN [Symbol]

AREA STATEMENT

	SQFT	SQM
TOTAL SITE EXTENT	2871.00	266.72
STILT CAR PARKING 4 Nos	624.00	57.99
GROUND FLOOR	1020.00	94.88
FIRST FLOOR	1803.25	167.70
SECOND FLOOR	921.06	85.66
HEAD ROOM	114.37	10.63
TOTAL FLOOR AREA	3744.33	348.22
PLOT COVERAGE	62.80%	
F.S-1	1.30	

PLAN SHOWING THE PROPOSED CONSTRUCTION OF THE RESIDENTIAL FLAT AT PLOT NO:46pt,47pt,KANNAPPA NAGAR 2nd ST., SURVEY NO:93/6, T.S.NO:166pt,167pt & 169, BLOCK NO:35, OF THIRUVANMIYUR VILLAGE CHENNAI-41, DIVISION NO: ZONE NO.

OWNER SIGNATURE

1. AKSHAY KUMAR SHARMA [Signature]
 2. PRABHAT KUMAR [Signature]
 3. GANGADHARAN [Signature]

V. BALASUBRAMANI, B.Arch., A.I.I.A., M.C.A.
 ARCHITECT & VALUER.
 GOVT. OF INDIA REGD. VALUER CI/407/88-89
 Regd. No. 10712 Council of Architecture
 Class I Licensed Surveyor R. A. No: 3
 CORPORATION OF CHENNAI.
 No: 3, Paper Mills Road, First Floor,
 NEAR PERAMBUR CHURCH, CHENNAI-600 011.

LICENSED SURVEYOR