



Planning Permit No. A/000 669/155/2001
APPROVED
 SUBJECT TO THE CONDITIONS IN THIS OFFICE LETTER.
 No. A/16433/2001 (13.6.01)
 12/6

SPECIFICATION
 Foundation :- Using p.c.c 1:5:10 below the brick footing with c.m. 1:5
 Super structure :- Brick in c.m. 1:5 for 4 1/2" tk R.C.c 1:2:4 for Lintel, beam, sunshade and roof slab
 Floor :- P.c.c 1:5:10 4 1/2" tk
 Flooring :- Mosaic flooring
 Roof :- R.C.c 1:2:4 4 1/2" tk
 Finishers :- Interior and exterior with cement paint
 Weathering course :- Using brick jelly lime concrete over two layers of weathering tiles

JOINERY DETAILS
 MD T.W. Frame main door 3'-3"x7'-0"
 D1 C.W. Frame Flush door 3'-0"x7'-0"
 D2 C.W. Frame Flush door 2'-6"x7'-0"
 W1 C.W. Glazed window 4'-6"x4'-6"
 W2 C.W. Glazed window 3'-6"x4'-6"
 W3 C.W. Glazed window 3'-0"x4'-6"
 Kw Kitchen window 2'-6"x3'-6"
 V Ventilator 2'-0"x3'-0"

W/R - WARDROPE
 ① & ② 5'-0"x2'-0" = 10.00 Sq.Ft.

AREA STATEMENT

	Sq.ft.	Sq.M.
Plot area	2772.00	257.86
Ground floor area	1172.00	109.03
First floor and upper ground floor area	1796.44	167.11
Upper first floor area	718.78	66.87
Total buildup area	3687.22	343.00
F.S.I Allowed 1.5	F.S.I Achieved 1.33	
Plot coverage 64.8 %		
Portico	573.56	53.36

COLOUR INDEX
 Pro. building [] Boundary line []
 Road [] Water line []
 Sewer line []

PROPOSED RESIDENTIAL BUILDING AT
 PLOT NO: K & J IN S.NO: 33/ 1A1A4
 SALIGRAMAM DHANALAKSHMI COLONY
 (EXTENSION NO:1) V.NO:110 SALIGRAMAM
 VILLAGE, SAIDAPET TAUK IN DIVISION NO:129
 ZONE VIII CHENNAI-600 093

Stilt cum Ground, First and Upper first floor plan and Terrace plan
 Site and Key plans, Elevation and Section plans
 Details of column footing, foundation & percolation pit

Scale :- 1" = 8'-0" Date = 2-05-2001

OWNERS SIGNATURE
M. K. S. Rajanathan Habeshi

LICENSED SURVEYOR
 S. ATHIYAMAN, B.E.
 Chartered Engineer
 Class - I Licensed Survey No 11179
 Corporation of Chennai
 MYSA, Thiruvahar Nagar, Thiruvahar
 CHENNAI - 600 041