



Planning Permit No. **A/000804/290/2001**
APPROVED
 SUBJECT TO THE CONDITIONS IN THIS OFFICE LETTER.
 No. **A/24965/BSP/21/12-2001**
 FOR MEMBER SECRETARY
 CHENNAI METROPOLITAN
 DEVELOPMENT AUTHORITY
 CHENNAI - 600 008.

Schedule of joinery

No	Width	Height	Description
D	3'3"	7'0"	T.w panel door
D1	3'0"	7'0"	T.w panel door
D2	2'6"	7'0"	Flush door
W	6'0"	4'6"	T.w glazed window
W1	5'0"	4'6"	-Do-
W2	3'0"	4'6"	-Do-
KW	4'0"	3'0"	-Do-
KW1	3'0"	3'0"	-Do-
V	2'0"		W.C. ventilator

- SPECIFICATION**
- P.C.C IN C.C 1:4:8
 - R.C.C in 1:2:4
 - 230 mm Brick work in cm 1:5
 - 115 mm Brick work in cm 1:5
 - Plastering the ceiling in cm 1:3
 - Plastering the walls in cm 1:4
 - Weathering course in brick jelly lime concrete with a course of flat tiles.
 - The O.H.T is scientifically closed.
 - The U.C sump is scientifically closed.
 - All w.c's in ground floor raised by 0.91m from ground level.

Area statement

Proposed construction	Sq.ft	Sq.m
Plot area	3202.00	297.48
Ground Floor Area	1350.00	125.42
First Floor Area	2054.90	190.90
Second Floor Area	1108.17	102.95
Total Builtup Area	4513.07	419.27
F.S.I. Applied for	1.409	
Plot coverage	64.8%	

- Legend**
- Proposed construction
 - Boundary line
 - Roads
 - Sewer line
 - Water line

OWNER
[Signature]

JOB TITLE
 Proposed Residences at
 Plot No: C-436, D.No: 26,
 46th street, Ashok Nagar,
 Chennai-600 083, bearing
 S.No: 64, Block No: 57,
 kodambakkam Village,
 Corporation division No: 114.

Scale : 1"=8'0" Date : 16-11-2001

Licensed Surveyor:
[Signature]
 N. GOPINATHAN
 Consulting Civil Engineer
 Licensed Surveyor
 CLASS-II, L.S. No: 135/00-01
 Corporation of Chennai
 9, R. R. Puram Street
 Kodambakkam, Chennai-600 024
 Phone: 4841352

