



Schedule of joinery

No	Width	Height	Description
D	3'3"	7'0"	C.W Door
D1	3'0"	7'0"	C.W Door
D2	2'6"	7'0"	C.W Door

W 116" x 6" Glazed window
 W1 3'0" x 7'0" Glazed window
 W2 C.No. A/15926/03 C.W Glazed window
 V also 3'0" x 7'0" Glazed window
 Slatting Plan

- SPECIFICATION**
1. R.C.C IN C.C 1:4:8
 2. R.C.A.P. in 1:2:4
 3. 230 mm Brick work in cm 1:5
 4. 115 mm Brick work in cm 1:5
 5. Plastering the ceiling in cm 1:3
 6. Plastering the walls in cm 1:4
 7. Weathering course in brick jelly lime concrete with a course of flat tiles.
 8. The O.H.T is scientifically closed.
 9. The U.G sump is scientifically closed.
 10. All w.c's in ground floor risid by 0.91m from ground level.

Area statement

Proposed construction:	Sq.ft	Sq.m
Plot area	3450.00	320.51
Ground Floor Area	1547.25	143.74
First Floor Area	2239.96	208.10
Second Floor Area	655.94	60.94
Total Builtup Area	4443.15	412.78

F.S.I. Applied for : 1.288
 Plot coverage : 64.9%

- Legend**
- Proposed construction
 - Boundary line
 - Roads
 - Sewer line
 - Water line

OWNER :

JOB TITLE
 Plan Showing the Proposed Residential Building at Plot No:2606, New D:NO:4 (Old D:No:44) AJ Block 4th Street, Anna Nagar, Chennai-40 Comprised in S.Nos:67(Part),88(Part) & 92 (Part) Of Naduvakkara Village, Egmore-Nungambakkam Taluk, Chennai District, Zone - V Division -66

Scale : 1"=8'0" Date : 27-05-2003

Licensed Surveyor:

V. SRINIVASAN, A.I.A.
 Registered Architect - CA/88/19755
 Licensed Surveyor-Corporation of Chennai R.A. No. 344
 Q-Block No. 37, 17th St. Anna Nagar, Chennai - 600 040. Ph: 2 628 6529

