



No	Width	Height	Description
D	3'-3"	7'-0"	T.W.Pannel Door
D1	3'-0"	7'-0"	T.W.Pannel Door
D2	6'-6"	7'-0"	Flush Door
W	10'-1/2"	4'-6"	T.W.Glazed window
W1	10'-0"	4'-0"	DO
W2	10'-0"	4'-0"	DO
V	2'-0"	3'-0"	ventilator

CMDA B-1 NO. 1
C. No. B-2/15130/03
Asst.

- SPECIFICATION**
- P.C.C. 1:4:8
 - R.C.C. 1:2:4
 - 230 mm Brick work in cm 1:5
 - 115 mm Brick work in cm 1:5
 - Plastering the ceiling in cm 1:3
 - Plastering the walls in cm 1:4
 - Weathering course in brick jelly lime concrete with a course of flat tiles.
 - The O.H.T is scientifically closed.
 - The U.G.sump is scientifically closed.
 - All w.c's in ground floor riser by 0.91m from ground level.

Area statement

	Sq.ft	Sq.m
Plot area (as per plan)	4413.24	410.00
Proposed construction:		
Ground Floor Area	1433.31	133.15
First Floor Area	1712.75	159.12
Second Floor Area	1712.75	159.12
Third Floor Area	1712.75	159.12
Total Builtup Area	6571.56	610.51
F.S.I. Applied for	1.480	
Plot coverage	38.81%	

- Legend**
- Proposed construction
 - Boundary line
 - Roads
 - Sewer line
 - Water line

OWNER:

[Signature]

JOB TITLE
PLAN SHOWING THE PROPOSED CONSTRUCTION OF DWELLINGS AT NEW No:47, (OLD No: 22), KAMARAJ AVENUE, 1st STREET, ADYAR, CHENNAI - 600 020. PALLIPATU VILLAGE, MYLAPORE- TRIPLICANE TALUK, T.S.No:4, BLOCK No:11, DIVISION No:151, ZONE-10, DEMOLITION SANCTION No:D10 / DA / 340 / 2003, DATE :- 26-05-2003.

Scale : 1"=80" Date : 15.05.2003

Licensed Surveyor:

[Signature]

V. SRINIVASAN, A.I.A.
Registered Architect - CA/98/19765
Licensed Surveyor - Corporation of Chennai
R. A. No. 344
Q-Block No. 37, 17th St, Anna Nagar,
Chennai - 600 040. Ph: 2 628 6529