

PLAN SHOWING THE PROPOSED ADDITIONS TO THE EXISTING RESIDENTIAL BUILDING AT HIGH BLOCK NO.372, TEMPLE COLONY, 15 TH MAIN ROAD, S.NO.207 PART OF KOYAMBEDU VILLAGE, ANNA NAGAR, CHENNAI-40

3<sup>rd</sup> R.P. dt. 16.11.07  
As per 1/2828/107

OFFICE COPY

- SPECIFICATION**
- FOUNDATION WITH P.C.C 1:4:8 OVER 6" SAND FILL
  - BRICK WALL IN FOUNDATION 1.5 MX
  - R.C.C 1:2:4 PLINTH BEAMS ALL ROUND
  - 9" & 4 1/2" THICK BRICK WORK IN SUPER STRUCTURE 1:6
  - PLASTERING IN C.M. 1:5 ON BOTH SIDES
  - ROOFING WITH R.C.C 1:2:4
  - WEATHERING COURSE LAID TO SLOPE
  - FLOORING WITH P.C.C 1:4:8 AND TOP FINISHED WITH MOSIC TILES
  - INSIDE WHITE WASH AND OUTSIDE COLOUR WASH
  - ALL WOOD WORK ARE OF BEST SEASONED WOOD PAINTED TWO COATS

**AREA DETAILS**

	SQ. FT.	SQ. MT.
PLOT AREA	7273.76	676.00
EXISTING GROUND FLOOR	1833.50	170.40
EXISTING FIRST FLOOR	1833.50	170.40
EXISTING SECOND FLOOR	1833.50	170.40
PROPOSED GROUND FLOOR	368.57	34.25
PROPOSED FIRST FLOOR	368.57	34.25
PROPOSED SECOND FLOOR	368.57	34.25
TOTAL	6606.21	613.85
PLOT COVERAGE	30.27%	
FLOOR SPACE INDEX	0.91	

**SCHEDULE OF JOINERY**

MD	MAIN DOOR	3'-3" X 7'-0"	1.00 X 2.13
D <td>DOOR</td> <td>3'-0" X 7'-0"</td> <td>0.91 X 2.13</td>	DOOR	3'-0" X 7'-0"	0.91 X 2.13
DC <td>DOOR</td> <td>2'-6" X 7'-0"</td> <td>0.76 X 2.13</td>	DOOR	2'-6" X 7'-0"	0.76 X 2.13
W <td>WINDOW</td> <td>5'-0" X 4'-6"</td> <td>1.52 X 1.37</td>	WINDOW	5'-0" X 4'-6"	1.52 X 1.37
W1 <td>WINDOW</td> <td>4'-0" X 4'-6"</td> <td>1.22 X 1.37</td>	WINDOW	4'-0" X 4'-6"	1.22 X 1.37
V <td>VENTILATOR</td> <td>3'-0" X 2'-0"</td> <td>0.91 X 0.76</td>	VENTILATOR	3'-0" X 2'-0"	0.91 X 0.76

**COLOUR CODE**

[Solid Line]	EXISTING BUILDING
[Dashed Line]	PROPOSED BUILDING
[Dotted Line]	EXISTING ROAD
[Dash-dot Line]	SITE BOUNDARY

SCALE - 1"=8'-0"  
DATE 15.11.2003  
DRAWN BY : MURUGAN

372/1 *Murali*  
372/2 *Sahayappa*  
372/3 R. *Murugan*  
372/4 *Sugunadevi*  
372/5 *P. Jeyapalan*  
372/6 *M. Sathish*  
OWNERS

**MR. E. MANJULUR RAMANAPADAR**  
Chartered Engineer  
Class-I, Licensed Surveyor - No. 773  
Department of Chennai  
City, Suburban & Rural Surveyors,  
Chennai - 600 001, India. - 99410 69033  
LICENSED SURVEYOR

