

S.No	WIDTH	HEIGHT	DESCRIPTION
D	3'-0"	7'-0"	W PANEL DOOR
D1	3'-0"	7'-0"	W PANEL DOOR
D2	2'-6"	7'-0"	W FLUSH DOOR
W	3'-0"	4'-0"	FRENCH WINDOW
W1	3'-0"	4'-0"	C.W GLAZED WINDOW
W2	3'-0"	4'-0"	C.W GLAZED WINDOW
V	2'-0"	2'-0"	C.W GLAZED WINDOW

- SPECIFICATIONS**
1. P.C.C IN M.C. 1:4:8
 2. R.C.C IN M.C. 1:2:4
 3. 230MM BRICK WORK IN C.M 1:5
 4. 115MM BRICK WORK IN C.M 1:5
 5. PLASTERING THE CEILING IN C.M 1:3
 6. PLASTERING THE WALL IN C.M 1:4
 7. WEATHERING COURSE IN BRICK JELLY LIME CONCRETE WITH A COURSE OF FLAT TILES
 8. THE O.H.T IS SCIENTIFICALLY CLOSED
 9. THE U.G SUMP IS SCIENTIFICALLY CLOSED
 10. ALL W.C'S IN GROUND FLOOR RAISED BY 0.90 M FROM G.L.
 11. PROVISION FOR SOLAR WATER HEATER SYSTEM 700 LPD

AREA STATEMENT

	SQ.FT	SQ.M
PLOT AREA	3600.00	334.45
PROPOSED CONSTRUCTION		
GROUND FLOOR AREA	1287.00	119.57
FIRST FLOOR AREA	1538.86	142.96
SECOND FLOOR AREA	1538.86	142.96
TOTAL BUILTUP AREA	4364.72	405.49

F.S.I APPLIED FOR 1.212
PLOT COVERAGE 42.75%

LEGEND

PROPOSED CONSTRUCTION

BOUNDARY LINE

ROADS

OWNER

Job Title:
Plan Showing the Proposed Apartments at Plot No 1184 P.No 9 G-Block 1st Street Anna Nagar, Chennai - 40. Bearing R.S.No 207/Part Kayambedu Village Chengleput District. ZONE - V DIVISION No: 64

SCALE: 1:100 DATE: 12-06-04

LICENSED SURVEYOR

V. SRINIVASAN, A.I.A.
Registered Architect - CA/551/19755
Licensed Surveyor - Corporation of Chennai
R.A. No. 344
Q-Block No. 37, 17th St. Anna Nagar,
Chennai - 600 040. Ph: 2 628 6529

