



SCHEDULE OF JOINERY

No	Width	Height	Description
D	3'-3"	7'-0"	D.M.P. Glass door
D1	3'-0"	7'-0"	C.W. Glass door
D2	2'-6"	7'-0"	C.W. Flush door
W	5'-0"	4'-0"	C.W. Glazed window
W1	4'-0"	4'-0"	C.W. Glazed window
W2	3'-0"	3'-0"	C.W. Glazed window
v	2'-6"	3'-0"	V.R. Gate

AP. D.P.

- Specification**
- R.C.C. in M. 25 grade
 - R.C.C. in M. 25 grade
 - 230 mm Brick work in cm 1:5
 - 115 mm Brick work in cm 1:5
 - Plastering the ceiling in cm 1:3
 - Plastering the walls in cm 1:4
 - Weathering course in brick jelly lime concrete with a course of flat tiles.
 - The O.H.T. is scientifically closed.
 - The U.G. sump is scientifically closed.
 - All w.c.'s in ground floor rise by 0.9m from ground level.
 - Provision for Solar Water Heater System 700 L.P.P.

Area statement

Area statement	Sq.ft	Sq.m
Plot area	4950.00	459.86
Proposed construction:		
Ground floor Area	1649.86	153.27
First Floor Area	1911.07	177.54
Second Floor Area	1911.07	177.54
Third Floor Area	1911.07	177.54
Total Builtup Area	7383.07	685.89
F.S.I. Applied for	1.492	
Plot coverage	38.61%	

- Legend**
- Proposed construction: [Symbol]
 - Boundary line: [Symbol]
 - Roads: [Symbol]
 - Sewer line: [Symbol]
 - Water line: [Symbol]

OWNER:

[Signature]

JOB TITLE
 Plan Showing the Proposed Apartments at Plot No. 1, Old D.No. 13, New D.No. 88 Brewery Road, Shenoy Nagar West Chennai - 30 Bearing R.S. No. 16/2, T.S. No. 44/7, Block No. 11, Periyakudal Village & Division, Egmore-Nungambakkam Taluk, Chennai District. Zone - B. Division no. 67.

Scale: 1" = 8'-0" Date: 16.03.2004

Licensed Surveyor:

V. Srinivasan, A.I.A.
 Registered Architect - CA/58/19755
 Licensed Surveyor - Corporation of Chennai R.A. No. 344
 Q-Block No. 37, 17th St. Anna Nagar, Chennai - 600 040. Ph: 2 628 5523