



OFFICE COPY
A/27/067/2005
Planning Permit No.
APPROVED
SUBJECT TO THE CONDITIONS IN THIS ORDER, LETTER No. A/080/05/02-02-02
FOR MEMBER SECRETARY
CHENNAI METROPOLITAN
DEVELOPMENT AUTHORITY
CHENNAI-600 003.

- SPECIFICATION:**
- Foundation in R. C. C. Columns over P.C.C. & Sand.
 - Bk. work in S. Structure, basement and parapet wall etc. to be in C.M. 1:6.
 - R.C.C. Plinth beam, lintel, sunshade and roof slab etc. to be in C.C. 1:2:4.
 - Mosaic flooring in C.M. 1:4.
 - Plastering of wall in C.M. 1:4.
 - All wood work are in teak and country wood.
 - Weathering course in L.M. and two course of flat tiles laid to slope.

SCHEDULE OF JOINERY :

TYPE	DESCRIPTION	SIZE
MD	MAIN DOOR	1.07 X 2.13
ED	ENTRANCE DOOR	1.07 X 1.90
D	DOOR	0.91 X 2.13
D1	DOOR	0.76 X 2.13
DI/W2	DOOR WINDOW	0.76 X 1.31 / 2.2 X 1.22
W	WINDOW	1.83 X 1.22
W1	WINDOW	1.52 X 1.22
W2	WINDOW	1.22 X 1.22
W3	WINDOW	0.91 X 1.22
W4	WINDOW	0.61 X 1.22
KW	KIT WINDOW	1.22 X 0.91
V	VENTILATOR	0.60 X 0.91

AREA STATEMENT:

PLOT EXTENT:	4079 Sqft.	378.95 Sqm.
GROUND FLOOR:	1344.88 Sqft.	124.94 Sqm.
FIRST FLOOR:	2646.29 Sqft.	245.83 Sqm.
SECOND FLOOR:	1316.79 Sqft.	122.33 Sqm.
TOTAL:	5307.96 Sqft.	493.12 Sqm.
PROVIDED F.S.I.:	1.30	
PLOT COVERAGE:	64.87%	

COLOUR INDEX:

PROPOSED ROAD: [Symbol]

SITE BOUNDARY: [Symbol]

PLAN SHOWING FOR THE PROPOSED RESIDENTIAL BUILDING (PLOT-A) AT DOOR Nos.6,7,8&9, NOOR VEERASAMY STREET, NUNGAMBAKKAM, CHENNAI-34. T.S.Nos: 372/2pt, 372/3pt, 372/4, 373/2pt, & 373/3pt, BLOCK No: 26, DIV:108, ZONE-07, NUNGAMBAKKAM DIVISION, EGMORE-NUNGAMBAKKAM TALUK, CHENNAI DISTRICT.

SCALE: 1" = 8'0" (1:100)

NORTH POINT: OWNER

G. Chandra m...
[Signature]

LICENSED SURVEYOR:

S. ATHIYAN, N.E.
Class-I, Licensed Surveyor No. 192
Corporation of Chennai
5, Natham Street, V. Nagar,
Chennai - 67. Phone: 2815 0224
Mobile: 31038440

