



JOINERY DETAILS	
DESCRIPTION	QTY
M1 door	1.00X2.13
M2 door	0.91X2.13
D2 door	0.76X2.13
W window	1.29X1.37
W1 window	0.60X1.37
W2 window	1.22X0.91
W3 window	1.22X0.91
V ventilator	0.60X0.91

- SPECIFICATIONS**
1. Column foundation over a concrete bed of mix 1:5:10 and b.w in c.m 1:6
 2. 230th b.work in cm 1:6 and 115th partition walls in cm 1:4
 3. All roc works are in cc 1:2:4 mix
 4. Ceramic tile flooring in all areas
 5. Weathering course in lime mortar with two course of pressed tiles
 6. Plastering in cm 1:4 in all faces of walls and distempered.

AREA STATEMENT	(sq.m.)	(sq.ft.)
Plot Area	356.57	3840.00
Ground floor	148.77	1600.00
Still Parking	68.54	737.50
First floor	231.24	2488.21
Second floor [Part]	85.71	919.08
Head Room	10.88	114.75
Total Proposed area	465.43	5008.07

COLOUR INDEX	
Proposed	—
Road	—
Boundary of site	—

PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING, AT DOOR NO. (NEW NO. 113, OLD 26), PLOT 'A', BLOCK NO. 8 & 23, SIVANKOIL STREET, KODAMBAKKAM, CHENNAI-24 IN T.S. NO. 1/12 & 37, PULIYUR VILLAGE, EGMORE-NUNGAMBAKKAM TALUK, CORPORATION OF CHENNAI, CORP. DN. NO. 118, ZONE VIII [SUB-DIVISION PLAN APPROVED VIDE NO. SD/WDC/08/0603/05, dt. 14-7-05 CORPORATION OF CHENNAI]

all dimensions are in metre centimetre and feet inches
scale = 1/100 or 1"=8'-0" date 18.07.2005

NAVEN PLANNERS
No. 20/7, Muthurangan Salai,
T. Nagar Chennai - 600 017
Phone - 26255697, Cell - 94440 21197.

signature of owner

signature of licensed surveyor

ER. K. SELVAM,
M.E. (CIVIL), AMIE., C. Eng (I), FIV,
REGISTERED ENGINEER & APPROVED VALUER,
CLASS I LICENSED SURVEYOR,
Reg No: 600/2005-2006,
DOOR No: 11/205 - 11th BLOCK,
MNDAPPAI EAST, CHENNAI-600 037
(NEAR MGR ADARSH SCHOOL)
PHONE No: 26562050 52252054
CELL - No: 9841282050