



FRONT ELEVATION




SECTION "AB"




KEY PLAN (NOT TO SCALE)


Inspection plan  
 x The existing building demolition works are under progress  
 x The proposed work not yet commenced  
 x Shutting road is 24' wide and public  
 x St lights available  
 x Drainage available



COMPOUND WALL DETAILS




PERCOLATION PITS DETAILS




COLLECTION SUMP FOR STORING RECYCLING SULLAGE WATER

U.G. SUMP




COLLECTION SUMP FOR RAIN WATER HARVESTING


COLLECTION SUMP FOR STORING RECYCLING SULLAGE WATER TO REUSE FOR TOILET SIZE 7'0" X 5'0" X 6'0" (HERMETICALLY SEALED)




STILT CUM GROUND FLOOR PLAN/SITE PLAN




FIRST FLOOR PLAN



SECOND FLOOR PLAN ( PART )



TERRACE FLOOR PLAN



FOUNDATION DETAILS

PLAN SHOWING THE PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING AT NEW DOOR NO.- 13, OLD DOOR NO.- 13B, ALAGIRI NAGAR 2ND STREET, VADAPALANI, CHENNAI - 26. IN T. S. NO.- 61/39, BLOCK NO.- 2 plan, PULIYUR VILLAGE, DIVISION - 117, ZONE - VIII

SCALE: 1:100 (or) 1" = 8'-0"

SPECIFICATION 99x57  
 FOUNDATION CONCRETE USING P.C.C 1:4:8 OVER SAND  
 FILLING BRICK WORK IN C.M 1:5 FOR 23 CM WALLS AND IN C.M 1:4 FOR 11 CM WALLS WALL PLASTERING IN C.M 1:4 AND CEILING PLASTERING IN C.M 1:3 R.C.C FOR ROOF SLAB, FLINTH BEAM, LINTEL, LOFT, SUN SHADE, ETC. IN C.C 1:2:4 FLOORING WITH MOSAIC TILES WEATHERING COURSE USING B.I.C IN LIME MORTAR WALL PAINTING 3 COATS USING CEMENT BASED PAINT PAINTING WOOD WORK WITH ENAMEL PAINTING OVER ONE COAT OF PRIMER.

SCHEDULE OF JOINERIES


D	DOOR	3'-3" x 7'-0"	1.00 x 2.13 (sq.m)
D1	DOOR	3'-0" x 7'-0"	0.91 x 2.13 (sq.m)
D2	DOOR	2'-6" x 7'-0"	0.76 x 2.13 (sq.m)
W	WINDOW	5'-0" x 4'-6"	1.52 x 1.37 (sq.m)
W1	WINDOW	4'-6" x 4'-6"	1.37 x 1.37 (sq.m)
V	VENTILATOR	2'-0" x 2'-0"	0.61 x 0.61 (sq.m)

AREA STATEMENT

PLOT AREA	3020.00 SQ.FT	283.34 SQ.M
PRO.G.F AREA	1040.00 SQ.FT	96.61 SQ.M
PRO.F.F AREA	1960.00 SQ.FT	182.08 SQ.M
PRO.S.F AREA ( PART )	1045.00 SQ.FT	97.08 SQ.M
HEADROOM AREA	155.00 SQ.FT	14.39 SQ.M
PLOT COVERAGE	64.26%	
F.S.I	1.32	

NON - F.S.I.

PRO. STILL PARK AREA	800.00 SQ.FT	74.32 SQ.M
----------------------	--------------	------------



POWER OF ATTORNEY

POWER OF ATTORNEY  
 K. Chinnathurai, D.C.E.,  
 Consulting Civil Engineer  
 Class-A, Licensed Surveyor  
 Corporation of Chennai  
 Reg. No. 219/2004-05  
 OM MURUGA PLANNERS  
 New No. 11, Old No. 45, Vengalpet Road, St. ARJUNABAKAM, CHENNAI - 600 104.  
 LICENSED SURVEYOR