



**SCHEDULE OF JOINERY**

TYPE	DETAIL	WIDTH	HEIGHT
MD	COUNTRY WOOD FLUSH DOOR	975	2100
D1	COUNTRY WOOD FLUSH DOOR	900	2100
D2	COUNTRY WOOD FLUSH DOOR	750	2100
FD	FRENCH DOOR	2400	2100
O	OPENING	750	2100
W	COUNTRY WOOD GLAZED WINDOW	1800	1250
WI	COUNTRY WOOD GLAZED WINDOW	1200	1350
KW	COUNTRY WOOD GLAZED WINDOW	1200	1950
V	COUNTRY WOOD GLAZED VENTILATOR	600	900

**SPECIFICATION**

FOUNDATION	: R.C.C COLUMN FOOTINGS
BRICK WORK	: C.M. 1:6 FOR SUPER STRUCTURE
PLASTERING	: C.M. 1:5 FOR WALLS & 1:3 FOR CEILING
FLOORING	: MOSAIC FLOORING
CEMENT PAINT	: 2 COAT FOR WALLS & 1 EXTRA COAT FOR CEILING
R.C.C.	: 1:2:4 FOR SLABS & LINTELS
WOOD WORK	: ALL WOOD WORKS IN BEST QUALITY TIMBER
WEATHERING	: BLENDED LIME MORTAR OVER ROOF COURSE
COURSE	: SLAB ONE LAYER OF COUNTRY TILES

**COLOUR INDEX**

PROPOSED	[Color Box]
ROAD	[Color Box]
BOUNDARY	[Color Box]
DEMOLITION	[Color Box]

**AREA STATEMENT**

AREA STATEMENT	SQ.MT
TOTAL SITE EXTENT	409.049
GROUND FLOOR	132.641
FIRST FLOOR	264.539
SECOND FLOOR (PART)	139.59
<b>TOTAL AREA</b>	<b>536.770</b>
<b>F.S.I = 1.312</b>	<b>COVERAGE = 64.67%</b>

**PROPOSED RESIDENTIAL BUILDING AT PLOT NO. 16-B, CORPORATION DOOR NO. 21, SRINIVASAMURTHY AVENUE, ADYAR, CHENNAI-600 020. IN L.A. NO. 143/73, OLD SURVEY NO. 13/2 AND 14/2 NEW T.S. NO. 25/15, CORPORATION DIVISION NO. 151, BLOCK NO. 40, IN KOTTUR VILLAGE, MYLAPORE-TRIPPLICANE TALUK**

**OWNER/POWER OF ATTORNEY SIGNATURE**

[Signature]

**ARCHITECT**

W. ANAND  
B.Arch., M.T.E.M., A.I.A.  
ARCHITECT & PROJECT CONSULTANT  
Council Reg. No. CAIE  
18, 8th Cross St.  
Indira Nagar, Adyar  
Chennai - 600 020

**W. ANAND**  
E-MAIL: anandarchitect@yahoo.com TEL / FAX: 52116272

CMDA "A" CHANNEL  
C.No. A2/5026/05  
Subj: Plan / Revised Plan  
P.A.I.  
[Signature]