



D/SPL.B.L.D.A. 2/14/2005
 Planning Permit No. 22/6616/2005
APPROVED
 SUBJECT TO THE CONDITIONS IN THIS OFFICE ORDER.
 FOR MEMBER SECRETARY
 CHENNAI METROPOLITAN
 DEVELOPMENT AUTHORITY
 CHENNAI - 600 095

OFFICE COPY
 CMDA (B) - No. 1
 No. 22/6616/2005
 Scrutiny P.A. 24/6/05
 TO VELACHERY
 TO MOOVANAR PETTAI
 PROPOSED SITE
 VIGNESWARA NAGAR FIRST STREET (DOY)
 P.D.M.A. VIGNESWARA NAGAR
 Revised Plan
 Dt: 23-6-05
 D.P.

SAND FILLING IN FOUNDATION 91.5 X 63.5
 P.C.C 1:4:8 IN FOUNDATION
 BRICK WORK IN CM 1:5
 R.C.C WORK IN 1:1.5:3 MIX
 PLASTERING IN CM 1:4
 WEATHERING COURSE WITH BRICK JELLY LIME CONCRETE

JOINERIES

D	MAIN DOOR	3'3" X 7'0"	1.00 X 2.13
D1	DOOR	3'0" X 7'0"	0.91 X 2.13
D2	DOOR	2'6" X 7'0"	0.76 X 2.13
W	WINDOW	4'0" X 4'0"	1.22 X 1.22
W1	WINDOW	6'0" X 4'0"	1.83 X 1.22
V	VENTILATOR	2'0" X 2'0"	0.61 X 0.61
O	OPENING	3'0" X 7'0"	0.91 X 2.13
R/S	ROOFING SHUTTER	6'0" X 7'0"	2.44 X 2.13

AREA DETAILS

	SQ.FT.	SQ.MT.
PLOT EXTENT (AS ON SITE.)	8708.21	809.02
PLOT EXTENT (AS PER PLR.)	9149.32	850.00
GROUND FLOOR	3346.33	310.88
FIRST FLOOR	4092.05	380.16
SECOND FLOOR	4092.05	380.16
	11530.43	1071.20
NON F.S.I	663.50	61.64

F.S.I = 1.32

REFERENCE

PROPOSED ROAD

BOUNDARY

SCALE : 1" = 8'0"
 1 : 100

PLAN SHOWING THE PROPOSED RESIDENTIAL CUM COMMERCIAL BUILDING (BANK) IN PLOT No. 1A, 1B & 12, DOOR No.1, VIGNESWARA NAGAR, MEDAVAKKAM MAIN ROAD CHENNAI, AT S.No.85/2 (AS PER DOC) 85/59 & 85/60 (AS PER PATT) OF ULLAGARAM VILLAGE, THAMBARAM TALUK, KANCHIPURAM DIST. ULLAGARAM - PUZHUTHIVAKKAM, THIRD GRADE MUNICIPALITY

OWNER'S SIGNATURE

S. ANITHY, B.E.,
 CHARTERED ENGINEER,
 CIVIL ENGINEER, No. 193
 17, Anna Salai, Chennai
 Contact: 23421224
 Mobile: 9840340

LICENSED SURVEYOR