

- SPECIFICATIONS:**
- FOUNDATION: P.C.C. 1:4:8 WITH BRICK FOOTING.
 - FLOORING: MOSAIC FLOORING OVER P.C.C. 1:4:8
 - WALLS: BRICK WORK WITH 1:3 PLASTERING
 - WEATHERING COURSE WITH LIME AND CEMENT MORTAR WITH PRESSED TILES.
 - WOOD WORK WITH TEAK AND COUNTRY WOOD.

SCHEDULE OF JOINERY

D - PANELLED DOOR	- 3'6" x 7'0"	(1.06x 2.13)
D1 - PANELLED DOOR	- 3'0" x 7'0"	(0.91x 2.13)
D2 - PANELLED DOOR	- 2'6" x 7'0"	(0.76x 2.13)
W1 - GLAZED WINDOW	- 6'0" x 4'6"	(1.83x 1.37)
W2 - GLAZED WINDOW	- 4'0" x 4'6"	(1.22x 1.37)
KW - GLAZED WINDOW	- 4'0" x 3'0"	(1.22x 0.91)
V - LOUVERED VENTILATOR	- 3'0" x 2'0"	(0.91x 0.61)

AREA STATEMENT (IN SQ.FT.) (IN SQ.M.)

AS ON SITE	7395.00	687.02
AS PER PIR	7373.34	685.00
GROUND FLOOR AREA	371.57	34.52
FIRST FLOOR AREA	2683.17	249.27
SECOND FLOOR AREA	2767.65	257.12
THIRD FLOOR AREA	2767.65	257.12
FOURTH FLOOR AREA	2431.56	225.90
TOTAL FLOOR AREA	11021.60	1023.93
PLAT COVERAGE PROVIDED	37.45%	
F.S.I	1.495	

CAR PARKING-

NOS OF CAR REQUIRED	8
NOS OF CAR PROVIDED	8

COLOUR INDEX:

ROAD	WATER LINE
PROPOSED	SEWER LINE
BOUNDARY	

SHEET NO - 1
SCALE : 1"=8'0"(1:100)
DATE : 31-05-05
DRAWN :
CHKD :

PLAN SHOWING THE PROPOSED RESIDENTIAL/DEPARTMENTAL STORE AT T.S.NO:3130/17 OF BLOCK NO:52 PURASAWALKAM, PERAMBUR TALUK, DOOR NEW NO:2/OLD NO:12, GAJAPATHY ROAD, KILPAUK.

OWNER
L. L.
L. DURAI BABU
LICENSED SURVEYOR

OSCAR CONCESSAO
M. Assn (USA) R.A.I.C. (Canada) A.T.I.A.
LICENSED SURVEYOR No. R.A. 333
Class I Corporation of Madras
C.A. / 47/1235
No. 1, Vivekananda Road, Sriharipuram,
Chennai, Chennai-600 011.
Phone No. 28361982

