



CM No. 31 No. 1
RC/10628/05
S. Anand
P.A. 2/1/15
19/10/05

SCHEDULE OF JOINERY			
TYPE	DETAIL	WIDTH	HEIGHT
M1	COUNTRY WOOD FLUSH DOOR	975	2100
D1	COUNTRY WOOD FLUSH DOOR	900	2100
D2	COUNTRY WOOD FLUSH DOOR	750	2100
O1	OPENING	750	2100
W1	COUNTRY WOOD GLAZED WINDOW	1800	1350
W2	COUNTRY WOOD GLAZED WINDOW	1200	1350
W3	COUNTRY WOOD GLAZED WINDOW	914	1350
K1	COUNTRY WOOD GLAZED WINDOW	1200	1050
V1	COUNTRY WOOD GLAZED VENTILATOR	600	900

91x50

SPECIFICATION	
FOUNDATION	R.C.C COLUMN FOOTINGS
BRICK WORK	C.M 1:4 FOR SUPER STRUCTURE
PLASTERING	C.M 1:5 FOR WALLS & 1:3 FOR CEILING
FLOORING	MOSAIC FLOORING
CEMENT PAINT	2 COAT FOR WALLS & 1 EXTRA COAT FOR CEILING
R.C.C	1:2:4 FOR SLABS & UNITS
WOOD WORK	ALL WOOD WORKS IN BEST QUALITY TIMBER
WEATHERING	BULLY LIME MORTAR OVER ROOF
COURSE	SLAB ONE LAYER OF COUNTRY TILES

COLOUR INDEX:	
PROPOSED ROAD	[Color swatch]
BOUNDARY	[Color swatch]

AREA STATEMENT	SQ.MT
TOTAL SITE EXTENT	445.931
STILT FLOOR	16.791
FIRST FLOOR	206.591
SECOND FLOOR	202.354
THIRD FLOOR	202.354
TOTAL AREA	628.09
F.S.I = 1.403	COVERAGE = 45.37%

PLAN SHOWING THE PROPOSED BUILDING AT DOOR NO. NEW NO.23, OLD NO.11, SRINIVASA STREET, T.NAGER, CHENNAI-600 017. IN PLOT NO.2, OLD SURVEY NO.151/1, T.S.NO.5767, (D.O.C) T-5-NO-9095 (PATTI) BLOCK NO-150, MAMBALAM, GUINDY, T. CORP. DIV NO.137, ZONE-9

DRAWN: K. SURESH
DATE: 30/3/05
SCALE: 1:100
FILE: NATWEST CORP.

OWNER/POWER OF ATTORNEY SIGNATURE
S. Anand
K. Natarajan

ARCHITECT
W. ANAND
ARCHITECT & PROJECT CONSULTANT
18, 5th Cross Street,
Indira Nagar, Adyar,
Chennai - 600 020.
TEL: 28 44 4211/12/13
W. ANAND
E-MAIL: anandarchitect@yahoo.com TEL / FAX: 52114272