

CMDA (B) / No. 1
C No. 61/1963/05

SCHEDULE OF JOINERY:

TYPE	DETAIL	WIDTH	HEIGHT
M.D	C.W. PANELLED DOOR	990	2135
D	-DO-	915	2135
D1	-DO-	762	2135
W	C.W. GLAZED WINDOW	1830	1372
W1	-DO-	1524	1372
W2	-DO-	1220	1372
O	OPENING	915	2135
V	C.W. GLAZED VENTILATOR	810	915

SPECIFICATION:

- FOUNDATION : R.C.C COLUMN FOOTINGS
- BRICK WORK : C.M 1:6 FOR SUPER STRUCTURE
- PLASTERING : C.M 1:5 FOR WALLS & 1:3 FOR CEILING
- FLOORING : MOSAIC FLOORING
- CEMENT PAINT : 2.COAT FOR WALLS & 1.EXTRA COAT FOR CEILING
- R.C.C : 1:2:4 FOR SLABS & LINTELS
- WOOD WORK : ALL WOOD WORKS IN BEST QUALITY TIMBER
- WEATHERING : B.JELLY LIME MORTAR OVER ROOF SLAB ONE LAYER OF COUNTRY TILES

COLOUR-INDEX:

PROPOSAL	
ROAD/STREET	
BOUNDARY/SITE	

AREA STATEMENT SQ. M

PLOT EXTENT (SITE)	1111.77
PLOT EXTENT (PATTI)	1125.00
STILT FLOOR	17.09
FIRST FLOOR	412.89
SECOND FLOOR	412.89
THIRD FLOOR	412.89
FOURTH FLOOR	412.89
TOTAL BUILTUP AREA	1668.65
PLOT COVERAGE:	36.98%
F.S.I	1.499

PROPOSED RESIDENTIAL BUILDING
S.S.R. PANGAJAM ROAD,
OLD S.NO: 143/1 PART, 143/2 PART,
144/1 PART & 144/2 PART,
T.S.NO:120, BLOCK NO: 38, OF
SALIGRAMAM VILLAGE, EGMORE-
NUNGAMBAKKAM, CHENNAI-93.
DIV. NO:129 ZONE : VIII

SCALE	1/8" = 1'-0"
-------	--------------

SIGNATURE OF OWNER

ER. K. SELVAM,
BE (CIVIL), AME, 74 (840) CIV.
CHARTERED ENGINEER & APPROVED VALUER,
CLASS 1 LICENSED SURVEYOR,
REG. NO: 602/2006-06,
DOOR NO: 11, 120, 11TH BLOCK,
MOGAPPAR EAST, CHENNAI 600 037,
TAMIL NADU (SALIGRAMAM SCHOOL).
LICENSING SURVEYOR
REG. NO: 602/2006-06

