



தகவல் வரைபடம்  
No. 20.2.06

செ. பெ. வ. கு. (பி) எண்  
ந. எண் 151-1-உசக-4/06  
உத்தியோக  
தி. உ. 2/2/06  
உ.தி.அ.

SCHEDULE OF JOINERY			
TYPE	DETAIL	WIDTH	HEIGHT
MD	COUNTRY WOOD FLUSH DOOR	990	2100
D1	COUNTRY WOOD FLUSH DOOR	900	2100
D2	COUNTRY WOOD FLUSH DOOR	750	2100
W	COUNTRY WOOD GLAZED WINDOW	1800	1350
W1	COUNTRY WOOD GLAZED WINDOW	1200	1350
W2	COUNTRY WOOD GLAZED WINDOW	1200	1050
KW	COUNTRY WOOD GLAZED WINDOW	650	1050
KW1	COUNTRY WOOD GLAZED WINDOW	1200	1050
O	OPENING	762	2100
V	VENTILATOR	900	900

94 X 50.3

SPECIFICATION	
FOUNDATION	1 R.C.C. COLUMN FOOTINGS
BRICK WORK	1 C.M 1:6 FOR SUPER STRUCTURE
PLASTERING	1 C.M 1:5 FOR WALLS & 1:3 FOR CEILING
FLOORING	1 MOSAIC FLOORING
CEMENT PAINT	1 2 COAT FOR WALLS & 1 EXTRA COAT FOR CEILING
R.C.C	1 1:2:4 FOR SLABS & LINTELS
WOOD WORK	1 ALL WOOD WORKS IN BEST QUALITY RUMBER
WEATHERING	1 B.JELLY LIME MORTAR OVER ROOF
COURSE	1 SLAB ONE LAYER OF COUNTRY TILES

COLOUR INDEX:	
PROPOSED	
ROAD	
BOUNDARY	

AREA STATEMENT	SQ.MT
TOTAL SITE EXTENT(PATTA)	506.32
STILT FLOOR	17.68
FIRST FLOOR	194.62
SECOND FLOOR	194.62
THIRD FLOOR	194.62
FOURTH FLOOR	150.81
<b>TOTAL AREA</b>	<b>752.30</b>
<b>F.S.I = 1.48</b>	<b>COVERAGE = 38%</b>

PROPOSED RESIDENTIAL BUILDING AT DOOR NO.32, CLUB ROAD, CHETPET, CHENNAI-600 031 IN R.S.NO.451/28, BLOCK NO-26 OF EGMORE VILLAGE. DIVISION - 104 ZONE - 7

	DRAWN : Kobi mran	DATE : 24.08.05	SCALE : 1:100	FILE : CLUP HOUSE
--	-------------------	-----------------	---------------	-------------------

OWNER/POWER OF ATTORNEY SIGNATURE

ER. K. SELVAM,  
BE, (Civil), AMIE, C.Eng(D), FIV,  
CHARTERED ENGINEER & APPROVED VALUER,  
CLASS-I LICENSED SURVEYOR,  
Reg No: 600/2005-2006,  
DOOR No: 11/206 11th BLOCK,  
NOGAPPAI EAST, CHENNAI-600 037  
(NEAR, MGR ADARSH SCHOOL)  
PHONE No: 26552950 35252050  
LL No: 9841282050