



**TITLE:**  
OFFICE COPY  
PLAN SHOWING THE PROPOSED ADDITIONAL CONSTRUCTION OF RICE MILL BUILDING WITH INSTALLATION OF 30 H.P IN S.No. 148/1B3, AS PER PATTI, C.No. 2, PUDU NAGAR, 3RD STREET, LAYONGRANT VILLAGE, PUZHUL PANCHYAT UNION, AMBATTUR TALUK, THIRUVALLUR DISTRICT.

**SPECIFICATIONS**  
C.C 1:5:10 USING 40mm HBG METAL IN FOUNDATION  
BRICK WORK WITH C.M 1:5 IN MASONRY WORKS  
R.C.C 1:2:4 MIX IS USED FOR ALL R.C.C WORKS  
PLASTERING WITH C.M 1:5:10 MIX  
FLOORING WITH C.M 1:3 OVER P.C.C 1:4:8  
ROOFING WITH A.C SHEET IN RICE MILL SHEET  
R.C.C IN WORKERS QUARTERS  
COLOUR WASHING 2 COATS

**SCALE : 1:100**

**JOINERY DETAILS**

RS	ROLLING SHUTTER	80"x80"	2.44x2.44
D	T.W. PANNELED DOOR	30"x70"	0.91x2.13
W	T.W. GLAZED WINDOW	50"x40"	1.52x1.37
W1	T.W. GLAZED WINDOW	40"x40"	1.22x1.37
V	VENTILATION	50"x20"	1.52x0.61

**MACHINERY DETAILS**

S.NO	ITEM	H.P
01.	SOLO ELEVATOR.	2.00
02.	PADDY CLEANER.	2.00
03.	PADDY SEPERATOR.	3.00
04.	RICE CONE 3'-0" Ø.	12.00
05.	RICE SHAKER.	2.00
06.	HUSK BLOWER.	2.00
07.	ELEVATOR.	2.00
08.	SHAKER.	2.00
09.	BOILING TANK.	3.00
	<b>TOTAL H.P</b>	<b>30.00</b>

**AREA STATEMENT**

	SOFT	SQM
PLOT EXTEND (DOCUMENT)	41632.57	3867.76
PLOT EXTEND [PATTI]	41661.42	3851.96
EXG RICE MILL FLOOR AREA	1635.25	151.92
PRO-RICE MILL FLOOR AREA	2147.75	199.53
WORKERS QUARTERS	440.00	134.15
TUBS	472.50	43.90
TOTAL FLOOR AREA	4695.50	436.22
PLOT COVERAGE	11.3%	-
FSI	0.11	-

**COLOUR INDEX**

DEMULISH	[Color Box]
PROPOSED	[Color Box]
ROAD	[Color Box]
BOUNDARY	[Color Box]

**LICENSED SURVEYOR**  
S. ATTIVAYAN, B.E.  
Civil & Surveying, No. 102,  
67, Madhav Street, T. Nagar,  
Chennai-17. Ph: 26166224,  
Mobile: 91366440.

**OWNER'S SIGN:**  
M. Krishnamoorthy  
M. Srinivasan