



அலுவலகப் படி
திட்ட வரைபட அனுமதி எண்: ..
...
உட்பளிக்கப்பட்டது
இவ்வலுவலகப் படித் திட்டம் 12.10.2018
நாள் 2.08.11.18...ல் குறுநில அமைச்சர்
வாரியாரைக் கருதி உட்பட்டது
...
உறுப்பினர் செலவுக்காக
செலவிடப்பட்ட பணத்தின் தொகை
...
600 000

Schedule of Joineries.

D36	1.07 X 2.13	Panelled Door
D3	0.91 X 2.13	Panelled Door
D26	0.76 X 2.13	Panelled Door
W5	1.52 X 1.52	Window
W4	1.22 X 1.52	Window
W3	0.91 X 1.52	Window
FW89	2.79 X 1.98	French Window
FW86	2.59 X 1.98	French Window
FW76	2.32 X 1.98	French Window
FW66	1.96 X 1.98	French Window
FW46	1.37 X 1.98	French Window
FW36	1.00 X 1.98	French Window
V2	0.60 X 0.60	Ventilator

PLAN SHOWING THE PROPOSED CONSTRUCTION OF STILT+3 FLOORS RESIDENTIAL BUILDING AT OLD DOOR NO-3, NEW DOOR NO-5, RAJAJI 1st STREET, NUNGAMBAKKAM, CHENNAI- 600 034
IN R.S.NO- 592/2 (AS PER DOCUMENT) 12/10/18
T.S.NO - 686/2 (AS PER PATTA)
BLOCK NO-34, NUNGAMBAKKAM VILLAGE, EGMORE, NUNGAMBAKKAM TALUK, CHENNAI DISTRICT, GREATER CHENNAI CORPORATION, ZONE - 9, DIV - 110.

Specifications:

Foundation	RCC Column footing grade of Concrete M20
R.C.C. Work	For Lintel, Beams, sunshade, Roof, etc., with required thickness cement concrete used M-25 grade
Super Structure	B.W in C.M 1:5
Flooring	Mosaic Floor
Joinery	Best Indian Country Wood
Finishes	Exterior & Interior painted with cement paint.
Weathering course	Brick jelly lime conc. below the weathering tiles

Area statement (sqm)

Plot Area (As per Patta)	422.50
Plot Area (As per Document)	423.63
Plot Area (As per Least)	422.50

Area Statement Sq.m

Floor Level	F.S.I. Area
Stilt floor area	
First floor area	209.31
Second floor area	209.31
Third floor area	209.32
TOTAL	627.94
F.S.I	1.486

No. of Car Parking Required = 6 Nos.
No. of Car Parking Achieved = 7 Nos.

Colour Index

Proposed	█
Boundary	█
Road	█

All Dimensions are in Metre.
Scale : 1:100

OWNER'S SIGNATURE
K. Kaveri

ARCHITECT'S SIGNATURE
V. KAVITHA

V. KAVITHA, Archt
THE G...
Old No. 16, New No. 8,
3rd Cross Street, Karapattam Garden,
Adyar, Chennai - 600 020.
Reg No. CA/2011/53298

