



அனுமதி அட்டை / **PERMIT TO CONSTRUCT**

| TYPE | DESCRIPTION | SIZE |
|-----------------|----------------|-------------|
| முகப்பு வளைப்பு | RAFT DOOR | 1.07 x 2.13 |
| புது | DOOR | 0.91 x 2.13 |
| D2 | DOOR | 0.76 x 2.13 |
| FD7 | FRENCH DOOR | 1.26 x 2.13 |
| W4 | WINDOW | 1.22 x 1.52 |
| W3 | WINDOW | 0.91 x 1.52 |
| KW3 | KITCHEN WINDOW | 0.91 x 0.90 |
| V | VENTILATOR | 0.60 x 0.60 |

- SPECIFICATIONS :-**
- R.C.C FOOTING & COLUMN IN CONCRETE M25
 - SUPER STRUCTURE - BRICKWORK SET IN cm 1:5
 - R.C.C M25 FOR LINTELS, BEAMS & SLABS
 - P.C.C 1:4:8 FOR FLOOR LEVELLING COURSE
 - P.C.C 1:5:10 IN BASEMENT FOR FOUNDATION
 - JOINERY WITH T.W FLUSH DOORS & T.W GLAZED WINDOWS & VENTILATORS
 - 3 COATS OF CEMENT PAINT TO INSIDE & OUT SIDE WALLS
 - 2 COATS OF ENAMEL PAINT OVER ONE COAT OF PRIMER FOR JOINERY, GRILL WORK, ETC
 - WEATHERING COURSE OVER ROOF SLAB 3" THICK WITH BRICK JELLY LIME CONCRETE AND ONE LAYER OF PRESSED TILES ON TOP

| AREA STATEMENTS | Sq.m |
|-------------------------|--------|
| PLOT AREA (AS ON SITE) | 470.92 |
| PLOT AREA (AS ON DOC) | 476.59 |
| PLOT AREA (AS ON PATTA) | 471.00 |

| | NON F.S.I AREA | F.S.I AREA |
|-------------------|----------------|------------|
| FIRST FLOOR AREA | 11.74 | 235.10 |
| SECOND FLOOR AREA | 11.74 | 235.10 |
| THIRD FLOOR AREA | 11.74 | 235.10 |
| TOTAL AREA | 35.22 | 705.30 |

F.S.I - 1.498

CAR PARKING REQUIRED - 6 NOS

CAR PARKING PROVIDED - 6 NOS

PLAN SHOWING THE PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING AT PLOT NO.3827, NEW DOOR NO.57, OLD NO.8, R-BLOCK, 6TH AVENUE, ANNA NAGAR, CHENNAI-600 040, COMPRISED IN R.S.NO.82 PART, T.S.NO.151, BLOCK NO.2 OF MULLAM VILLAGE, AMINJIKARAI TALUK, CHENNAI DISTRICT, ZONE-8, DIVISION-100

SCALE : 1:100 DATE : 27.02.2018

JOB NO : 28 DRAWN : K.VIJAYALAKSHMI

COLOUR INDEX

| | |
|---------------|--|
| PROPOSED ROAD | |
| BOUNDARY | |
| SEWER LINE | |

For INDIA BUILDERS (Chennai) LIMITED

C. Sanyal
Managing Director

APPLICANT'S SIGNATURE

LICENSED SURVEYOR

A. Vijayalshmi

A. VIJAYALAKSHMI, B.Arch
Registered Architect
Council of Architecture, CA /2009 / 45361
No: No. 165/1, Anna Nagar, Agraharam,
Korattur, Chennai-76.