



PLAN SHOWING THE PROPOSED RESIDENTIAL APARTMENT AT OLD DOOR NO.8, NEW DOOR NO. 15, O.S. NO. 1741 & 1739, R.S.NO.1649/1,(As per document) R.S.NO. 1649/50 (PATTA) BLOCK NO.34, SIR DESIKACHARI ROAD, MYLAPORE VILLAGE, MYLAPORE, CHENNAI - 600 004, CHENNAI DISTRICT, GREATER CHENNAI CORPORATION. ZONE : IX DIVISION: 123

**SPECIFICATION**  
SAND FILLING IN FOUNDATION  
PCC 1:4:8 IN FOUNDATION  
BRICK WORK IN CM 1:5  
RCC WORK M25 GRADE  
PLASTERING IN CM 1:4  
NOTE: MINIMUM CONCRETE GRADE USED IS - M25 [1:1:2]

**JOINERY DETAILS**

MD DOOR	3'6" X 7'0"	1.07 X 2.13
FD DOOR	6'0" X 7'0"	1.81 X 2.13
D1 DOOR	3'0" X 7'0"	0.91 X 2.13
D2 DOOR	2'6" X 7'0"	0.76 X 2.13
FW WINDOW	6'0" X 4'0"	1.81 X 1.22
W WINDOW	4'0" X 4'0"	1.22 X 1.22
W1 WINDOW	3'0" X 4'0"	0.91 X 1.22
KW WINDOW	4'0" X 3'0"	1.22 X 0.91
V VENTILATOR	2'0" X 2'0"	0.61 X 0.61

**AREA STATEMENT**

PLOT EXTENT	SQ.M
AS PER DOC	452.25
AS PER PATTA	450.00
AS PER SITE	446.06
AS PER SUPER IMPOSED	446.06

  

	FSI AREA (m) <sup>2</sup>	NON-F.S.I AREA (m) <sup>2</sup> (BALCONY)
FIRST FLOOR	194.35	9.45
SECOND FLOOR	194.35	9.45
THIRD FLOOR	194.35	9.45
FOURTH FLOOR	194.35	9.45
TOTAL	777.40	37.80

F.S.I =  $\frac{777.40}{446.06} = 1.743$

**REFERENCE**

- PROPOSED
- ROAD
- BOUNDARY

OWNER'S SIGNATURE: *K. Anita*

**LICENSED SURVEYOR**

**K. ANITHA, B.Arch.**  
Reg. No. CA/201/1637/18, Saidapet,  
No.1, Soodammanai Street, Saidapet,  
Chennai - 600 015, Ph: 98410 82999  
Email ID: anitha3468@yahoo.co.in