

திருச்சிபு வகுப்பம்
30-09-2019
OFFICE COPY
செ.பெ.வ.கு. (19)
பெ. என்.என்.என்.
பெ. என்.என்.என்.
பெ. என்.என்.என்.

SCHEDULE OF QUANTITIES

TYPE	DETAIL	QTY	UNIT
M.D	C.W. PANELLED DOOR	2135	
D	-DO-	2135	
D1	-DO-	762	
W	C.W. GLAZED WINDOW	1830	
W1	-DO-	1372	
W2	-DO-	1220	
O	OPENING	915	
V	C.W. GLAZED VENTILATOR	610	

SPECIFICATION:

FOUNDATION : R.C.C COLUMN FOOTINGS
 BRICK WORK : C.M 1:6 FOR SUPER STRUCTURE
 PLASTERING : C.M 1:5 FOR WALLS & 1:3 FOR CEILING
 FLOORING : MOSAIC FLOORING
 CEMENT PAINT : 2 COAT FOR WALLS & 1 EXTRA COAT FOR CEILING
 R.C.C : 1:2:4 FOR SLABS & LINTELS
 WOOD WORK : ALL WOOD WORKS IN BEST QUALITY TIMBER
 WEATHERING : B.JELLY LIME MORTAR OVER ROOF COURSE
 SLAB ONE LAYER OF COUNTRY TILES

AREA STATEMENT

PLOT AREA	AS PER PATTA	AS PER SITE	AS PER DOCUMENT
	700.00 Sqm	658.29 Sqm	679.39 Sqm

F.S.I : 1.030

FLOOR PART	AREA
GROUND FLOOR PART	190.92 Sq. m (Residential)
FIRST FLOOR	65.28 Sq. m (Office)
SECOND FLOOR	123.41 Sq. m
TOTAL FLOOR AREA	699.87 Sq. m

PLAN SHOWING THE PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING AT PLOT NO:1, DOOR NO:3, ANNA AVENUE, BAKHAVACHALAM NAGAR EXTN, ADYAR, CHENNAI-600020 IN T.S.NO: 46/1, BLOCK NO:16, PALLIPATTU VILLAGE, GREATER CHENNAI CORPORATION

ZONE XIII DIV : 175

COLOUR INDEX

PROPOSED	
BOUNDARY	
ROAD	

SIGNATURE OF OWNER

V. Jay

M. RENGANATHAN, I.E.
 CMDA Reg No: REGR-II/19/03/025
 Greater Chennai Corporation
 License No: RE2/00352019
 No.87/8, 1st Street, 1st Sector, K.K. Nagar
 Chennai - 600 078 / Cell: 9941874116
 Email: mrenanathan2019@gmail.com
 LICENSED SURVEYOR

