

<b>TOTAL EXTENT (AS PER DOCUMENT)</b>	:	<b>24403 SQ.M</b>
<b>ROAD AREA</b>	:	<b>7308 SQ.M</b>
<b>PARK AREA</b>	:	<b>1778 SQ.M</b>
<b>PUBLIC PURPOSE AREA (1%)</b>	:	<b>178 SQ.M</b>
<small>(P.P-1 HANDED OVER TO THE LOCAL BODY 0.5% AREA : 89.0 SQ.M) (P.P-2 HANDED OVER TO THE TANGEDCO 0.5% AREA : 89.0 SQ.M)</small>		
<b>REGULAR PLOTS ( 1 TO 134)</b>	:	<b>134 Nos.</b>
<b>E.W.S.PLOTS (1876 SQ.M) (135 TO 164)</b>	:	<b>30 Nos.</b>
<b>TOTAL NO.OF.PLOTS</b>	:	<b>164 Nos.</b>

**NOTE:**

- SPLAY-1.5MX1.5M
- MEASUREMENTS ARE INDICATED EXCLUDING SPLAY DIMENSION


- ROAD AREA
  - PARK AREA
  - PUBLIC PURPOSE AREA-1
  - PUBLIC PURPOSE AREA-2 (RESERVED FOR TANGEDCO)
- WERE HANDED OVER TO THE LOCAL BODY VIDE GIFT DEED DOCUMENT NO. 9592/2023, DATED: 12.12.2023, @ SRO TAMBARAM JOINT-1

**CONDITIONS:**

- THE APPLICANT SHOULD FOLLOW THE CONDITIONS MENTIONED BY THE CE, PWD/WRD, CHENNAI REGION, CHEPAUK, CHENNAI-5 IN LETTER NO.DB/T5(3)/F-9920 NOC- AGARAMTHEN VILLAGE / 2022/DATED.21.10.2022, WHICH ARE TO BE COMPLIED BY THE APPLICANT BEFORE ISSUING OF THE LAYOUT APPROVAL BY THE COMPETENT AUTHORITY (LOCAL BODY)
- The applicant's land should be filled with earth filling with proper compaction to the minimum Level of (+)12.500m (e) 1.6m above the crest level of Agaramthen tank at FTL (+) 10.900m, to protect the site from inundation during floods. The process of earth filling and compaction should be done in layers of not more than 030 metre depth to achieve required degree of compaction for the depth varying from 1.110m to 0.520m depending upon the existing field levels. Also, the applicants should provide emergency pumping operation for the seepage water, if it is proposed to have basement floor and as well as dewatering arrangements during flood periods
- The All round pavement level within the site should not be less than (+)12.500m. The applicants should prepare the layout proposal by considering the suitable internal storm water drainage network as Micro drain of suitable size (ie) peripheral drain of size not less than 1.00x0.90m, and lateral drains of suitable size within the site as per site condition and the same should be connected to the local drain/channel, rainwater harvesting roads with road side drains and sewerage treatment plant and its disposal and garbages / debris and other solid waste management as per norms in existence within the applicants land according to existing rules in force and should get proper approval from competent authority without fail
- The sewage or any unhygienic drainage (Treated or Untreated) should not be let into drain /channel/course at any cost and the debris and other materials should not be dumped into the drain/surplus course obstructing free flow of water The applicants should make drainage network, at their own cost and the same is to be connected to natural storm water drainage/channel
- The necessary setback distance (not less than 3m) especially on Eastern side should be provided with in the site as per site condition as per the norms in existence and as per the rules in force of CMDA (Circular issued by the office of the Commissioner of Town & Country Planning, Chennai-2 vide Roc No 4367/2019 -BA2/13.03 2019) during development and there should not be any Construction activities, in the set back areas in future also The CMDA should in the completion certificate only after compliance certificate from WRD
- The applicants should clearly demarcate the boundary of their land before the commencement of any developmental activities in the presence of Revenue & WRD authorities especially on Eastern side. The applicants should also maintain the measurement of the Site without any encroachments and should maintain as per Revenue records (FMB)
- The applicants should abide by the rules and regulation of the WRD from time to time The applicants should also abide court of law of both State & Central Government from time to time.
- The permission granted to the applicants, should not be altered/modified/changed to any others. Based on the records submitted by the applicants, the permission is granted. If any documents seem to be fake/manipulated/fabricated, in future the above permission will be cancelled without any correspondence. Hence, the applicants are solely responsible of genuinity of the documents submitted
- The WRD officers should be allowed to inspect the site at any time, during execution and thereafter, if necessary Advance intimation should be given to the WRD officers concerned before commencement of work
- The applicants should get clearance certificate for their site from the Revenue department to make sure that the site is not an encroached property from the water body as well as confirming this proposed site boundaries
- WRD is giving opinion only in connection with the inundation aspect and does not deliver any rights to the applicants to encroach the WRD/ Government Lands/ Channel
- The applicants should not object at any time for the maintenance works/ improvement works of the Government channels which are proposed to be carried out by WRD. The applicant should give an undertaking in writing to the effect that the above proposal will not obstruct in case any maintenance/improvement/development works as per Revenue records (FMB), which are proposed to be carried out by WRD in future periodically
- The sewage water from the applicant's land should not let into the drain and for the disposal of the sewage water, suitable arrangements should be made for the same by the applicant, and as well as the construction materials/debris/garbages should not be dumped into the channel/nver/tank at any cost. At any cost, sewage/sullage should not be let into river, and the garbages debris and construction materials should not be dumped into the channel/river restricting the free flow of water The trueneess of the document received from the applicants in respect to the ownership is purely of applicants responsibility and it is only for reference purpose to this department The legal validity of this document should be verified by the Development / Revenue authorities. The specific remarks on inundation are purely issued on technical grounds in respect to the physical location of land.
- Failing to comply with any of the above conditions, WRD reserves rights to withdraw the Technical opinion along with NOC on inundation point of view for the above proposed site and in event, the applicants shall not be eligible for any compensation whatsoever and as well as legal entity

**LEGEND:**

- SITE BOUNDARY
- ROADS GIFTED TO LOCAL BODY
- PARK GIFTED TO LOCAL BODY
- EXISTING ROAD
- PUBLIC PURPOSE-1 GIFTED TO LOCAL BODY
- PUBLIC PURPOSE-2 GIFTED TO LOCAL BODY (FOR TANGEDCO)
- EWS
- ERI



This Planning Permission Issued under New Rule TNCD BR.2019 is subject to final outcome of the W.P(MD) No.8948 of 2019 and WMP (MD) Nos. 6912 & 6913 of 2019.

**CONDITION:**  
THE LAYOUT APPROVED IS VALID SUBJECT TO OBTAINING SANCTION FROM THE LOCAL BODY CONCERNED.

**P.P.D** NO : **10**  
**L.O** **2024**

**APPROVED**

**VIDE LETTER NO** : LAYOUT-1 / 0198 / 2023  
**DATE** : 19 / 01 / 2024

**OFFICE COPY**  
FOR MEMBER SECRETARY  
CHENNAI METROPOLITAN  
DEVELOPMENT AUTHORITY



# ST. THOMAS MOUNT PANCHAYAT UNION

LAYOUT OF HOUSE SITES IN S.Nos. 238/1B, 2A1, 2A2, 2B1, 2B2, 3, 4, 5A, 5B, 6, 239/1B4A, 1B4B, 242/2A, 2B, 3, 4A, 4B2A2 & 242/4B2B OF AGARAMTHEN VILLAGE.

SCALE : 1:800 (ALL MEASUREMENTS ARE IN METRE.)