




**SITE EXTENT (AS PER DOCUMENT) = 4694 SQ.M**  
**ROAD AREA = 981 SQ.M**  
**PUBLIC PURPOSE PROVIDED = 40 SQ.M**  
P.P - 1 HANDED OVER TO THE LOCAL BODY (0.5% AREA : 20.0SQ.M)  
P.P - 2 HANDED OVER TO THE TANGEDCO (0.5% AREA : 20.0 SQ.M)  
**NO.OF PLOTS = 24 NOS**

**NOTE:**

- SPLAY - 1.5M x 1.5M
- MEASUREMENTS ARE INDICATED EXCLUDING SPLAY DIMENSIONS
- |   |  |
|---|--|
|  ROAD AREA<br> PUBLIC PURPOSE AREA-1<br><small>(RESERVED FOR LOCAL BODY)</small><br> PUBLIC PURPOSE AREA-2<br><small>(RESERVED FOR TANGEDCO)</small> | WERE HANDED OVER TO THE LOCAL BODY VIDE GIFT DEED<br>DOC. NO: 472 / 2024, DATED: 29.01.2024 @ SRO, POONAMALLEE |
|---|--|

**CONDITIONS :**

(I) THE APPLICANT SHOULD FOLLOW THE CONDITIONS MENTIONED BY THE CE, PWD, WRD, CHENNAI REGION, CHEPAUK, CHENNAI -5. LETTER NO.DB/T5(3)/F.004840 NOC-THIRUMAZHISAI VILLAGE 007464/2023/DATED:08.09.2023 ARE TO BE COMPLIED BY THE APPLICANT BEFORE ISSUING OF THE LAYOUT APPROVAL BY THE COMPETENT AUTHORITY (LOCAL BODY)

- The applicants' land should be filled with earth filling with proper compaction to the minimum level of (+)28.250m (i.e.) 0.190m above Weir Crest Level of Thirumazhisai Tank is (+)28.060m to protect the site from inundation during floods. The process of earth filling and compaction should be done in layers of not more than 0.30 metre depth to achieve required degree of compaction for the depth from (+)0.970m to (+)1.060m depending upon the existing field levels. Also, the applicants should provide emergency pumping operation for the seepage water, if it is proposed to have basement floor and as well as dewatering arrangements during flood periods. The all-round pavement level within the site should not be less than (+) 28.250m and the regular habitation should not be below MFL.
- The applicants should clearly demarcate the boundary of their land before commencement of any developmental activities in the presence of Revenue, Local body and WRD authorities concerned without fail and should not encroach the Channel in S. F. Nos. 107 on the Northern side of applicant site as per FMB and monitored and maintained by the applicant at their own cost. The Government Land should be maintained without encroachments as per Revenue records and the applicants should make necessary periodical arrangements for free flow of water through the existing Government Land to the downside area along the proposed site.
- The permission granted to the applicants, should not be altered / modified/ changed to any others. Based on the records submitted by the applicants, the permission is granted. If any documents seem to be fake / manipulated / fabricated, in future the above permission will be cancelled without any correspondence. Hence, the applicants are solely responsible of genuineness of the documents submitted.
- The WRD officers should be allowed to inspect the site at any time, during execution and thereafter, if necessary. Advance intimation should be given to the WRD officers concerned before commencement of work.
- The applicants should abide by the rules and regulation of the WRD from time to time. The applicants should also abide court of law of both State & Central Government from time to time.
- WRD is giving opinion only in connection with the inundation aspect and does not deliver any rights to the applicants to encroach the WRD / Government Lands / river. The NOC for this site from the WRD is purely issued on the basis of inundation point of view.
- The Channel in S.No.107 on Thirumazhisai village stretch abutting to the applicant boundary should be marked as per FMB and monitored and maintained by the applicant at their own cost. The width of the channel should be maintained without encroachments as per Revenue records and the hydraulic parameters of the field channel should be maintained. The applicants should make necessary periodical arrangements for free flow of water through the existing channel to the downside area along the proposed site. Also, the applicants should de-silt the channel periodically and remove the obstruction then and there, without any hindrance for free flow of water at their own cost within the proposed land, even after the completion of project also.
- The Channel in S. No. 107 on Thirumazhisai village of the applicant's land should be completely de-silted and re-sectioned by constructing retaining wall on Northern side as well as bed lining concrete of the drain as per the FMB at the applicant's own cost. The bed level of the above course should be ascertained and restored before commencing the development activity in the presence of the concerned WRD Executive Engineer. Moreover, the width of entire field drain as per Revenue records (FMB) along & within the stretch of applicant's land should be maintained properly without any change and no encroachments.
- The applicant should not object at any time for the maintenance work / improvements work of the channel which is proposed to be carried out by WRD. The applicant should give an undertaking in writing to the effect that the above proposal will not obstruct in case any maintenance / improvements / development works as per Revenue records (FMB), which are proposed to be carried out by WRD / Local body in future periodically.
- The applicants should not construct any cross masonry across the water body area without obtaining prior permission from WRD. If any damaged to the water body should be restored by the applicant at their own cost.

**Technical Suggestions**

- The applicant should prepare the layout proposal by considering the suitable internal storm water drainage network as micro drain of suitable size as per prevailing site conditions within the site. The same connected to the local drain / channel, rainwater harvesting, roads with road side drain and sewerage treatment plant and its disposal & garbages / debris and other solid waste management disposal as per norms in existence within the applicants' land according to the existing rules in force and should get proper approval from the competent authority without fail.  
 The sewage or any unhygienic (treated or untreated) should not be let into drain/channel/course at any cost and the debris and other materials should not be dumped into the drain/surplus course obstructing free flow of water. The applicants should make drain networks at their own cost and the same is to be connected to natural storm water drainage / channel. There should not be any hindrance to the free flow of internal drain to downstream.
- The applicant should provide necessary setback distance especially on North side within the site according to the site condition as per the norms in existence and as per the rules in force of CMDA (as per the circular issued by the office of the Commissioner of Town & Country Planning, Chennai-2 vide Roc.No.4367 / 2019-BA2 / Dated 13.03.2019) during development and there should not be any construction activities in setback areas in future also. The CMDA should issue completion certificate only after obtaining compliance certificate NOC from WRD.
- The applicants should get clearance certificate for this site from the Revenue department to make sure that the site is not an encroached property from the water body as well as confirming this proposed site boundaries.
- The sewage water from the applicants' land should not let into the drains and for the disposal of the sewage water, suitable arrangements should be made for the same by the applicant and as well as the construction materials/debris/garbage should not be dumped into the channel / river / Eri / Pond at any cost.  
 At any cost sewage/sullage should not be let into river / Eri / channel / Pond, and the garbage, debris and construction materials should not be dumped into the channel/river/Eri/Pond restricting the free flow of water.

The owner of the document received from the applicants in respect to the ownership is purely of applicant's responsibility and it is only for reference purpose to this department. The legal validity of this document should be verified by the Development / Revenue authorities. The specific remarks on inundation are purely issued on technical grounds in respect to the physical location of land.

Failing to comply with any of the above conditions, WRD reserves rights to withdraw the technical opinion on inundation point of view to the above proposed site and in event, the applicant shall not be eligible for any compensation whatsoever and as well as legal entity.

(II) LOCAL BODY SHOULD ENSURE COMPLIANCE OF ALL THE CONDITIONS STIPULATE BY WRD, PWD IN THEIR LETTER NO.DB/T5(3)/F.004840 NOC-THIRUMAZHISAI VILLAGE 007464/2023/DATED:08.09.2023, AND SHALL OBTAIN A LETTER FROM WRD CONFIRMING THE COMPLIANCE OF THE CONDITIONS BEFORE THE SANCTION AND RELEASE OF THE LAYOUT.

(III) TNCDDBR-2019 RULE NO: 47 (8) IN G.O.(Ms) No.18, MAWS DEPARTMENT DATED 04.02.2019 & AMENDMENTS APPROVED IN G.O.Ms.No.16, MAWS (MAI) DEPARTMENT DATED 31.01.2020 AND PUBLISHED IN TNGG ISSUE No.41, DATED:31.01.2020.

ONE PERCENT OF LAYOUT AREA EXCLUDING ROAD, ADDITIONALLY, SHALL BE RESERVED FOR "PUBLIC PURPOSE". WITHIN THE ABOVE CEILING 0.5% OF AREA SHALL BE TRANSFERRED TO THE LOCAL BODY AND 0.5% OF AREA SHALL BE TRANSFERRED TO THE TANGEDCO OR TO THE LOCAL BODY FREE OF COST THROUGH A REGISTERED GIFT DEED BEFORE THE ACTUAL SANCTION OF THE LAYOUT.







(IV) TNCDDBR-2019, RULE NO:47 (11)


THE COST OF LAYING IMPROVEMENTS TO THE SYSTEMS IN RESPECT OF ROAD, WATER SUPPLY, SEWERAGE, DRAINAGE OR ELECTRIC POWER SUPPLY THAT MAY BE REQUIRED AS ASSESSED BY THE CONCERNED AUTHORITY, NAMELY, THE LOCAL BODY AND TAMIL NADU ELECTRICITY BOARD, SHALL BE BORNE BY THE APPLICANT.

(V) THE APPLICANT IS RESPONSIBLE FOR THE SHAPE, SIZE & DIMENSIONS OF THE SITE UNDER REFERENCE.

© NECESSARY SPACE FOR BUILDING LINE TO BE LEFT AS PER THE RULE IN FORCE WHILE TAKING UP DEVELOPMENT IN EVERY PLOT.

**LEGEND:**

-  SITE BOUNDARY
-  ROAD GIFTED TO LOCAL BODY
-  EXISTING ROAD
-  PUBLIC PURPOSE - 1 GIFTED TO LOCAL BODY
-  PUBLIC PURPOSE - 2 GIFTED TO LOCAL BODY (FOR TANGEDCO)
-  CHANNEL



**THIRUMAZHISAI TOWN PANCHAYAT**  
**LAYOUT OF HOUSE SITES IN S.No: 105 / 1, 2, 3, 4, 5 OF THIRUMAZHISAI VILLAGE.**  
 SCALE : 1:800 (ALL MEASUREMENTS ARE IN METRE)

**CONDITIONS:**  
 THE LAYOUT APPROVED IS VALID SUBJECT TO OBTAINING SANCTION FROM THE LOCAL BODY CONCERNED.

**P.P.D NO : 58**  
**L.O NO : 2024**  
**APPROVED**  
 VIDE LETTER NO : LAYOUT-1 / 0134 / 2023  
 DATE : 14 / 03 / 2024

**OFFICE COPY**

FOR CHIEF PLANNER (LAYOUT)  
 CHENNAI METROPOLITAN  
 DEVELOPMENT AUTHORITY

This Planning Permission Issued under New Rule TNCDDBR.2019 is subject to final outcome of the W.P(MD) No.8948 of 2019 and WMP (MD) Nos. 6912 & 6913 of 2019.

